

Accessible Ramp
new accessible ramp created giving safe access into the churchyard. Ramp to be 1500mm wide, constructed from a porous buff coloured resin bound gravel with stone sett edgings. One car parking space on The Wyldie to be taken away in order to accommodate safe pedestrian movement. Formal metal barrier at 1000mm high to be erected between spaces to prevent parking

ledger stones taken up from around
the church to be moved and laid
around the boundary wall of the
churchyard

carry out minor repairs to existing
stone steps, copings and walls around
the church

existing raised tree pit and surrounding
flags to be removed to allow existing
failing ash tree to be fully removed;
new growing medium laid and a new
heavy standard tree to be planted in its
place. To include for new ornamental
tree grille and guard

existing flagged and stepped access
to memorial garden to be lifted and
relaid to form accessible ramp (height
difference 240mm over 9000mm)

new metal lectern style interpretation
panel to be installed at southern
entrance to Church. Exact position
and design to be agreed

concrete and macadam surface
repairs around War Memorial to be
replaced with new stone flags, cut to
fit around base of monument



Ref. 22

Ref. 23
Fraxinus excelsior

- Category A trees
- Category B trees
- Category C trees
- Category U trees
- existing tree to be felled
- line of proposed new drains
- new bound surface around the church
- repositioned ledges
- new resin bound path with stone edge
- existing lights
- proposed new lights

following tree survey, existing diseased and failing trees to be felled and replaced with new trees. See 'Proposals for Tree Works and Replacement Planting' document for full details.



Total of 31 existing trees surveyed; 15 trees to be removed

21 new trees planted around the site

supply aco drain (200x230mm deep) across bottom of access road, linked to new piped drain running beneath the new road adjacent to the church. Drain to connect to existing inspection chamber/manhole

existing graves and stones to be taken up from around the church and replaced with new porous bound surfacing material in a buff colour (likely to be resin bound gravel, budget permitting) allow better access for vehicles

existing sundial to be mounted on new stone paving replacing concrete flags. Stones to be inlaid with names of notable residents of Bury



scale 1:200@A2



Proffitts

Investing in Communities