



Agreement for Infrastructure Services Issue 8 revised 06 2019

openreach

Description of works

Scope of Works:

Provide a new 9M (Metre) light carrier pole in footway on Neath Close.

This to allow 2 x DW's (Drop Wire) serving 1 & 3 Neath Close to be re-routed, due to a proposed new extension at 48 Peveril close.

DW to 48 Peveril close will also need to be relocated to allow extension works to progress.

Poling:

Provide 9M light carrier pole in footway on Neath Close.

PEU (Pole Erection Unit) access is available.

Provide DW15 from DP778 (Distribution Point) to new CP (Carrier Pole), fit BT66B (Block Terminal) at pole top
Swing existing spans of DW from both number 1 & 3 Neath close onto the new CP, connect circuits through in
BT66B(Block Terminal).

Provide DW from DP778 to a new DW fixing on front elevation of 48 Peveril Close, connect to existing lead in using
AGC (Above Ground Closer).

Test all circuits on completion of the new cable works.

Recover redundant DW from DP778 to 48 Peveril Close.

