

Client: Harry Jackson
Site: Ferngrove House, Bury

Overview Report

Following our recent site visit, 28.2.23, please see below an engineer's report of the findings.

Our engineers attended site in order to carry out and complete a CCTV inspection to the exposed culvert on the site to determine the outfall location. Upon arrival we found the water level of the culvert to be above 50% therefore the camera unit was unable to obtain a clear image of the culvert, this being classed an incomplete survey. However, we can confirm that the culvert was flowing more than adequately despite the water level being above 50% of the diameter. We lifted a chamber cover located on Ferngrove and found this to be the next chamber downstream beyond/outside of the boundary. We were unable to locate the next chamber down for the run but would advise to contact the local authority or United utilities for any further information regarding the culvert as we understand it to not be the client/customer responsibility once the water course / drainage has left the site or crossed over a boundary line. See below the run of the culvert.



Should you have any queries then please do not hesitate to contact us.

Regards,

S. Horridge

The Drainage Group