




Lantern: Signify DigiStreet Medium NW 80LED 12.0Klm with DW10 optic, lantern post top mounted on 60mm spigot, to include CityTouch, with a minimum of 10 years subscription. Lantern to be fitted with 7-pin NEMA socket. Lantern to be mounted at 0° tilt.

Column: 10m Mallatite B4730 "Bury Sign" post top mounting column with 60mm spigot for the lantern to seat on. Columns are to be mounted at the rear of the footway or where there is no footway set back at 1.0m from the kerb edge.

Photocell: 1 part Zodion SS6, sealed to IP67, switching at 20 lux 1:1.

Supply: All columns must be fed via an Electricity North West (ENW) or other approved IDNO connection.

Numbering: Columns should be numbered with the numbers facing the road (in line with the lantern), and at a minimum height of 2m above ground level, numbers are available for collection, from the Bury Council street lighting office. The numbers shown on this drawing are for design purposes only the actual numbering should be approved by Bury Council.

ALL TO BE TO BURY COUNCIL DEPARTMENT OF OPERATIONS STREET LIGHTING SPECIFICATION VERSION 6. ALL STREET LIGHTING WORKS TO BE CARRIED OUT TO THE COUNCIL'S SPECIFICATIONS.

This lighting design has been prepared in accordance with the HEA-HEMSA Guidance Note – CDM2015 Regulations, issue 1.1, dated 09/04/15 Procedure 2.

The client has duties under regulations 9-10 of CDM 2015 please refer to the CDM2015 ACoP and HSE leaflet INDG 411 – "Need building work done? – A short guide for clients on the Construction (Design and Management) regulations 2015"

This lighting design is an outline design and has been prepared based on the information supplied by the client at the time of request. This does not include information on any hazards or risks present.

ALL STREET LIGHTING DUCTING TO BE IN ACCORDANCE TO NJUGS STANDARDS.

STREET LIGHT DUCTING

REV.	AMENDMENTS	DATE
P01	INITIAL ISSUE	12/02/24
P02	ROUNDABOUT LAYOUT AMENDED, STREET LIGHT DUCTING ADDED	06/03/24
P03	DROP OFF AMENDED	21/03/24

NOTES

- THIS DRAWING IS SUBJECT TO FULL CDM COMPLIANCE, STATUTORY UNDERTAKERS SEARCH/DIVERSION REQUIREMENTS, HIGHWAY DRAINAGE PROVISION, LAND OWNERSHIP AND LOCAL AUTHORITY APPROVAL. NO DEVIATION FROM THE DRAWING SHOWN IS ALLOWED WITHOUT WRITTEN PERMISSION
- REFER TO VIA SOLUTIONS PROJECT SPECIFIC DESIGN RISK ASSESSMENT (DRA)
- IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING WHERE APPROPRIATE TO AN APPROVED METHOD STATEMENT / LEGAL AGREEMENT



STAR RADCLIFFE ACADEMY
SPRING LANE BURY

PROPOSED STREET LIGHTING

SCALE: 1:250 @A1

DATE: MARCH 2024

DRAWING NO: FS1013-VS-XX-XX-D-H-0210

STATUS: S3 REVISION: P03