

PLANTING NOTES

01 - All planting shall be in accordance with BS.4428. 1989.S7.
02 - Trees shall conform to BS.3936-1.1992.
03 - Tree pits shall be 1200x1200x750mm.
04 - Multi stem pits shall be 1000x1000x600mm.
05 - Backfill material 70% certified sandy loam / 30% Approved tree compost (by volume).
06 - No peat products permitted.
07- Staking as indicated in plant schedules.
08 - Install Greentech Mona watering systems to trees.
09 - Shrub / Hedge planting : 400mm depth of free draining topsoil to BS.3882.
10 - Lawns : 150 mm depth of free draining topsoil to BS.3882.
11 - Wildflower : Onto clean unimproved free draining subsoil to BS.8601. Or approved Low nutrient soil.

PLANTING SCHEDULE

12812_PSCHD_v3.

		NO.	GIRTH cm	HEIGHT cm	TYPE	%	DENSITY per m2	NOTE
1.0	**TREES**							
T1	Acer campestre.	3	18-20	350-400	RB	NA	NA	Underground guyed.
T2	Betula pendula.	1	18-20	350-400	RB	NA	NA	Underground guyed.
T3	Betula Fastigiata Joe.	1	18-20	350-400	RB	NA	NA	Underground guyed.
T4	Prunus Sargentii Rancho.	3	18-20	350-400	RB	NA	NA	Underground guyed.
T5	Prunus avium.	1	18-20	350-400	RB	NA	NA	Underground guyed.
T6	Sorbus aucuparia.	4	18-20	350-400	RB	NA	NA	Underground guyed.
T7	Prunus amanogawa.	4	18-20	350-400	RB	NA	NA	Underground guyed.
2.0	**NATIVE HEDGE**							
	MIXED HEDGE							NH01 NH02 NH03 NH04
	Salix caprea.							
	Crataegus monogyna.	32	NA	60-80	BR	10	NA	3 9 13 7
	Malus sylvestris.	74	NA	60-80	BR	25	NA	7 21 29 17
	Sambucus nigra.	90	NA	60-80	BR	30	NA	9 25 35 21
	Ilex aquifolium.	16	NA	60-80	RB	5	NA	1 5 7 3
	Rosa canina.	32	NA	60-80	BR	10	NA	3 9 13 7
	Prunus spinosa.	16	NA	60-80	BR	5	NA	1 5 7 3
	Rosa arvensis.	32	NA	60-80	BR	10	NA	3 9 13 7
	Ligustrum vulgare.	16	NA	60-80	BR	5	NA	1 5 7 3
	Planted in a double staggered row, 1.0m wide.							
	85o plants per LM.							
	Planted in 100cm biodegradable grow tubes with support.							
	Underseeded wvith Emorsgate EH1 Hedgrow mix.							
3.0	**LOW DECORATIVE HEDGE**							
LDH	Euonymous japonicus Paloma Blanca.	320	NA	30-45	3L	NA	3	
4.0	**SHRUB MIX 01**							SM01/1 SM01/2 SM01/3 SM01/4 SM01/5 SM01/6
	Campanula portenschlaginca.	28	NA	NA	2L	10	5	5 9 3 7 3 1
	Euonymous fortunei Silver Queen.	26	NA	20-30	3L	15	4	7 9 3 3 3 1
	Hydranger annabelle.	12	NA	15-20	3L	5	1	1 2 3 2 3 1
	Lavandula intermedia phenomenal.	28	NA	30-45	5L	10	4	5 9 3 7 3 1
	Pennisetum Fairy Tales.	52	NA	20-30	3L	25	3	9 11 7 11 9 5
	Pachysandra terminalis.	28	NA	15-20	3L	10	4	5 9 3 7 3 1
	Stipa tenuissima.	48	NA	15-20	3L	25	3	7 11 7 11 7 5
5.0	**SHRUB MIX 02**							SM02/1 SM02/2 SM02/3 SM02/4 SM02/5 SM02/6
	Festuca glauca Elijah Blue.	35	NA	15-20	3L	10	4	3 6 7 7 3 9
	Hydranger annabelle.	16	NA	30-45	5L	5	1	1 3 3 3 3 3
	Lavandula angustifolia Arctic Snow.	54	NA	15-20	3L	20	4	5 9 11 11 5 13
	Phormium Cookianum Tricolour.	22	NA	30-45	5L	5	3	1 1 5 5 3 7
	Ophiopogon planiscopus Kokuryo.	35	NA	15-20	3L	15	4	3 6 7 7 3 9
	Potentilla fruticosa	36	NA	30-45	5L	15	3	3 7 7 7 3 9
	Stipa ichu	48	NA	15-20	3L	30	3	5 10 9 9 5 10
5.0	**WILDFLOWER**							
WF	Emorsgate WF4 Mix for Clayey Soils.							
6.0	**AMENITY LAWNS**							
AL	Hard WearingTurf.							

KEY

- **TREE PLANTING** SEE PLANT SCHEDULE FOR DETAILS
- **EXISTING HEDGE** RETAINED
- **NATIVE HEDGE PLANTING** SEE PLANT SCHEDULE FOR DETAILS
- **LOW DECORATIVE HEDGE** SEE PLANT SCHEDULE FOR DETAILS
- **SHRUB BEDS** SEE PLANT SCHEDULE FOR DETAILS
- **WILDFLOWER** SEE PLANT SCHEDULE FOR DETAILS
- **AMENITY LAWNS SEE PLANT SCHEDULE FOR DETAILS**
- **NON DEFINED AREA TO BE DEFINED**
- **MIXED SCRUB PLANTING** SEE PLANT SCHEDULE FOR DETAILS

NOTES

1. All to architect's and engineer's details.
2. All works to be DDA compliant.

N

SCALE 1 : 200

m 10 0 10 m

r5	WILDFLOWER/LAWN AMENDED	27,08,26 AP
r4	UPDATED TO J1192-WS-PL102-2	26,08,26 AP
r3	ADDITIONAL TREES / SIZE INCREASES FOR BNG	12,11,25 AP
r2	PLANTING AND SCHEDULE UPDATED	16,10,25 AP

NOTE:
1. Do not scale from this drawing.
2. All setting out, levels and dimensions to be agreed on site.
3. The dimensions of all materials must be checked on site before being laid out.

Project:
Springside Road
Walmersley

Title:
Soft works

AMENITYTREE
ENVIRONMENTAL PLANNING CONSULTANTS
Willow Cottage, School Lane, Burdwarsley, CH3 9NX. 01829 770 075

Status: Planning

First Issued: SEPT 2025 | Drawn: AP

Scale: 1:200 | Size: A1

Drawing No.:
AT.25.12812.101r5