

[illegible][illegible]

**MAXIMUM SITE SURFACE WATER FLOW
TO DIVERTED CULVERT (ORDINARY
WATERCOURSE) TO BE 5.4l/s (100 Yr +
45% CLIMATE CHANGE ALLOWANCE)**

**THIS DRAWING IS SUBJECT TO SECTION 104 &
SECTION 38 TECHNICAL APPROVALS.**

ALL CONNECTIONS TO THE ADOPTED
SYSTEM TO BE MADE AT LEVEL SOFFITS.

LEVELS ARE RELATED TO OSGM02
(OSGM02 CONVERTS GPS ELLIPSOID HEIGHTS TO
ORTHOMETRIC HEIGHTS ABOVE MEAN SEA LEVEL)

COORDINATES ARE RELATED TO NATIONAL GRID (GPS)

E	27/05/26	JSD	LAYOUT AND DRAINAGE UPDATED.
D	17/02/26	JSD	LAYOUT AND DRAINAGE UPDATED.
C	06/01/26	JSD	LAYOUT UPDATED AND PLOT DRAINAGE ADDED.
B	30/10/25	JSD	LAYOUT UPDATED (WATER BUTTS ADDED).
A	09/10/25	JSD	FOUL DRAINAGE/RISE MAIN UPDATED.

PRELIMINARY

CLIENT
EDGEFOLD HOMES

PROJECT
SPRINGSIDE ROAD
WALMERSLEY
BURY

EXTERNAL WORKS G.A.
SURFACE WATER & FOUL DRAINAGE

JOB No.		DRAWING No.		REVISION
J292		/ 103		E
DRAWN	CHECKED	SCALE	SHEET SIZE	DATE
JSD	MD	1:200	A0	SEPT 2025
DRAWING NOT TO BE SCALED				

Email: info@DandDconsulting.co.uk
 Web: www.DandDconsulting.co.uk
 Tel: 07884 975243 (J.Dickinson)
 07884 936577 (M.Davenport)

D and D
consulting engineers

D and D Consulting Engineers Ltd
Labyrinth Business Centre, 45 Middle Hillgate, Stockport SK1 3DG