

Notes

- Do not scale from this drawing on print or electronically. Work from figured dimensions only.
- No deviation from the details on this drawing is allowed without CampbellReith's prior permission in writing.
- Read this drawing with all Architect's, Service Engineer's and CampbellReith's relevant details, specifications and drawings.
- All work is to be done in accordance with the relevant specifications issued by CampbellReith, British Standard Codes of Practice, Statutory Requirements and the Contract Documents.
- Drawing revision:
P: Preliminary - Evolving drawings for approvals, tenders, billings etc.
C: Contractual - Drawings authorized and approved for stage completion.
- Drawing status:
Work in progress
S0 - Initial status
Shared (Non-contractual)
S1 - Suitable for coordination, **S2** - Suitable for information, **S3** - Suitable for review and comment, **S4** - Suitable for stage approval.
Published (For contractors purposes)
A1, A2 etc - Authorised and accepted ('n' relates to work stages)
B1, B2 etc - Partial sign-off (with comments)
CR - As constructed record document (Final Construction ONLY. Any deviations to that which is on site is not the liability of CampbellReith)
- Work Stages:
2 - Concept, **3** - Definition, **4** - Design, **5** - Build & commission, **6** - Handover
8 - Only drawings with revision **Cn** and status **A5** to be used for Construction.
- Topographical information provided by Inoral in February 2022
- TFGM boundary provided by TFGM in January 2023

LEGEND

- Cut
- Fill

SURFACE LEVEL DATA				
NUMBER	MINIMUM LEVEL	MAXIMUM LEVEL	COLOUR	AREA
1	-6.000	-5.000		21.873m²
2	-5.000	-4.000		177.075m²
3	-4.000	-3.000		353.549m²
4	-3.000	-2.000		546.529m²
5	-2.000	-1.000		765.359m²
6	-1.000	0.000		4306.021m²
7	0.000	1.000		5589.968m²
8	1.000	2.000		933.892m²
9	2.000	3.000		566.846m²
10	3.000	4.000		416.064m²
11	4.000	5.000		232.883m²
12	5.000	6.000		9.218m²

Cut/Fill Summary

Name	Cut Factor	Fill Factor	2d Area	Cut	Fill	Net
cut and fill west	1.000	1.000	13919.276sq.m	5776.597 Cu. M.	8120.016 Cu. M.	2343.419 Cu. M.<Fill>
Cut and Fill east	1.000	1.000	2091.037sq.m	1170.831 Cu. M.	419.022 Cu. M.	751.810 Cu. M.<Cut>
Totals			16010.313sq.m	6947.428 Cu. M.	8539.037 Cu. M.	1591.609 Cu. M.<Fill>

P2	Issued for information	26/06/24	LR
P1	Issued for information	15/02/24	NB
Rev	Description	Date	By

CampbellReith
consulting engineers

London020 7340 1700

Bristol0117 916 1066

☐ Manchester0161 819 3060

☐ Birmingham01675 467 484

www.campbellreith.com

Job Title	Pyramid Park Enabling Works
Client	Bury Council

Preliminary Earthworks Cut and Fill

Drawn byNB | Date made15/02/24 | Scale @ A01:250 | Checked byBT | SuitabilityS1 | CR Project14111

Project No14111 | OrigCRH | FunctXX | SpatialXX | FormDR | DiscC | Number5013 | RevP2