



TREE SCHEDULE

| TREES | Abbreviations | Species                         | Common Name                | Girth/Spacing | Height/Spread | Pot        | Quantity | Notes         | Native Status        | Carbon Performance Grade | Carbon Breakeven Point |
|-------|---------------|---------------------------------|----------------------------|---------------|---------------|------------|----------|---------------|----------------------|--------------------------|------------------------|
|       | Af            | Acer x freemanii 'Autumn blaze' | Field maple 'Autumn blaze' | 35-40cm       | 6-7m          | Rootballed | 1        | 2m clear stem | Subspecies of native | C                        | 4 Year                 |
|       | Af            | Acer x freemanii 'Autumn blaze' | Field maple 'Autumn blaze' | 25-30cm       | 5.5-6m        | Rootballed | 1        | 2m clear stem | Subspecies of native | C                        | 4 Year                 |
|       | Cb            | Carpinus betulus                | Hornbeam                   | 25-30cm       | 5.5-6m        | Rootballed | 3        | 2m clear stem | Native               | A                        | 3 Year                 |
|       | Ac            | Acer campestre 'Streetwise'     | Field maple 'Streetwise'   | 25-30cm       | 5.5-6m        | Rootballed | 2        | 2m clear stem | Subspecies of native | B                        | 1 Year                 |
|       | Sa            | Sorbus aucuparia                | Rowan                      | 20-30cm       | 5-5.5m        | Rootballed | 1        | 2m clear stem | Native               | C                        | 3 Year                 |
|       | Pa            | Prunus avium                    | Bird cherry                | 25-30cm       | 5.5-6m        | Rootballed | 1        | 2m clear stem | Native               | B                        | 1 Year                 |

**PLANTING NOTES:**

- Plant handing at the nursery, and transit up to delivery, shall be in accordance with 'Plant Handling' the booklet published by the Committee for Plant Supply and Establishment (CPSE). The contractor shall comply with comply with clauses 3 & 4 of the above booklet (obtained from the Horticulture Trades Association) which refers to the receipt, uploading and temporary storage of plants.
- Plants shall be first class examples of their species or variety, free from all pests and diseases with good fibrous roots systems and materially undamaged. (Refer to relevant sections of BS3556 Parts 1-4 'Specification of Nursery Stock').
- All planting is to be in general compliance with BS4428: 1989 'Code of Practice for general landscape operations (excluding hard surfaces)'.
- All trees are to be staked and secured. Underground guying detail to be agreed on site with Landscape Architect
- One number 80litre bag of tree planting compost (non peat based) is to be incorporated into each tree pit backfill material
- The contractor must ascertain for himself the exact location of any underground services and maintenance points.
- All areas of ornamental planting are to be mulched to consolidated depth of 50mm using medium grade tree bark.
- At the time of planting, shrub areas will be covered by a min. 450mm depth of good quality 'As Dug' topsoil in accordance with BS3882 (1994)
- Water as necessary to ensure the establishment and continued thriving of planted matter.
- Carry out all work when soil and weather conditions are suitable:  
i) Do not plant during periods of frost or strong winds. Plant only during the following periods:  
- Bare root deciduous trees and shrubs: Late October to late March  
- Container grown plants: At any time if ground water and weather conditions are favourable.  
Ensure that adequate watering and weed control is available.

Maintenance notes for trees and shrubs:

- Maintenance is to be carried out on a monthly basis (12mr annual visits) At each visit the following operations are to be carried out:  
a- Check and firm all planted material. Also check materials after stormy or windy conditions  
b- Check for pests and diseases and treat appropriately  
c- Remove all weeds and unwanted material via a combination of chemical and hand weeding operations  
d- Pick up all litter and remove all arisings from site  
e- Sweep all paths and roadways and dispose off site  
f- Remove any dead material from site  
g- Water as necessary to ensure the continuing health of all plants
- Carry out the following operations every 6 months:  
a- Apply an approved fertilizer to all planted material during spring and autumn  
b- Trim all hedges/sculptural planting in spring and autumn and remove arisings from site. Final height for clipped formal hedges 1250mm
- Carry out the following operations annually:  
a- During autumn or following flowering prune all shrub materials in accordance with good horticultural practice  
b- Top up all areas of bark mulch to a consolidated depth of 50mm  
c- Replace any material which has failed over the previous 12 months. All replacements are to be of equal specification as the original and the replacements schedule is to be agreed with the CA prior to implementation. Any deviation from the species list must be agreed with the CA.

**KEY:**

- Project Redline Boundary
- Unadopted Area
- Existing Site Structures - no proposed works
- EXISTING TREE RETAINED
- SEMI-MATURE TREE
  - Container grown
  - See Softworks drawing for more information
- SENSORY PLANTING
  - See planting schedule for information on sizes/density
  - Species as per sensory planting schedule on page
  - 50mm bark mulch to top
  - 300 topsoil
  - 200 subsoil
- ORNAMENTAL PLANTING
  - See planting schedule for information on sizes/density
  - 50mm bark mulch to top
  - 300 topsoil
  - 200 subsoil
- EXISTING BANDSTAND SEDUM ROOF
  - Product: Sedum Blanket System 5G502
  - Material: Pre-grown blanket of sedum planting on growing medium
  - Size: 151mm total depth, 25mm sedum, 80mm growing medium, 46mm drainage board and protection fleece
  - Supplier: Sky Gardens Green Solutions or equal and approved
  - Other: Sedum roof, drainage and fixing as per engineer's design and details. To use existing bandstand drainage points and discharge points.
- NATIVE HEDGEROW
  - Species: Hedge planting with native species.
  - Bushy form with no gaps.
  - Size: Maintained at 1000mm height, 1.2-1.5m rootballed single row.
  - Other: Timber post and wire fence to rear
  - Refer to Softworks schedule for more detail
- CLIMBING SPECIES
  - Species: Native, evergreen and flowering species to climb up tensile wire system.
  - See planting schedule for information on sizes/density
  - Other: To be supported by S31 tensile wire system affixed to building as per supplier's recommendations
  - See climber detail drawing for more information.

|        |            |                              |     |    |
|--------|------------|------------------------------|-----|----|
| S3-P13 | 28-06-2023 | Highway & Binstore updates   | RM  | RM |
| S3-P12 | 26-05-2023 | Stage 04 Issue               | JTO | RM |
| S2-P11 | 10-05-2023 | Interim Stage 04 Issue (WIP) | RM  | RM |
| S2-P10 | 23-02-2023 | BIN STORE SHOWN              | RM  | RM |
| S2-P09 | 17-02-2023 | FOR PLANNING                 | RM  | RM |
| S2-P08 | 27-01-2023 | STAGE 03                     | JTO | RM |
| S2-P07 | 17-10-2022 | STAGE 03                     | JTO | RM |
| S2-P06 | 05-08-2022 | STAGE 03                     | JTO | RM |
| S2-P05 | 19-07-2022 | STAGE 03                     | JTO | RM |
| S2-P04 | 16-06-2022 | STAGE 03                     | JTO | RM |
| S2-P03 | 10-05-2022 | STAGE 03                     | JTO | RM |
| S2-P02 | 25-01-2022 | STAGE 02                     | JTO | RM |
| S2-P01 | 20-01-2022 | STAGE 02                     | JTO | RM |

| Revision | Date | Description | Drawn | Appr. |
|----------|------|-------------|-------|-------|
|          |      |             |       |       |

**Planit I.E. Limited**  
E: info@planit-ie.com    W: planit-ie.com  
**MANCHESTER**  
2 Back Grafton St., Altrincham, WA14 1DY  
T: 0161 928 9281  
**LONDON**  
Unit 6 Waterside, 44-48 Wharf Road, London, N1 7UX  
T: 0207 253 5678  
**LIVERPOOL**  
Tempest 5.3, 12 Tithebarn Street, Liverpool, L2 2DT  
T: 0151 363 1230

|                            |                     |             |          |
|----------------------------|---------------------|-------------|----------|
| Client                     | Bury Council        |             |          |
| Project                    | Radcliffe Civic Hub |             |          |
| Drg Title                  | Softworks           |             |          |
| Created on                 | Created by          | Approved by |          |
| 04-01-2022                 | JTO                 | RM          |          |
| Scale                      | Size                | Workstage   |          |
| 1:200                      | A1                  | Stage 04    |          |
| Drg No.                    | Suitability         |             | Revision |
| RADHUB-PIE-00-00-DR-L-0004 | S3                  |             | P13      |