



**Drainage Strategy
And
Flood Risk Assessment
for
Proposed Development
Former Wheatfield Day Centre
Whitefield M45 6DP**

Client Name: Onward
Our ref: LRD31990
Date: July 2022
Revision: 001

SUTCLIFFE

Drainage Strategy & Flood Risk Assessment

DOCUMENT VERIFICATION

Report Reference: LRD31990

Issue: 01

Date: April 2022

Prepared by:

Name:	Dave Samuels
Title:	Executive Associate
Qualifications:	CEng MIStructE MAPS

Checked / Approved by:

Name:	Martin Pocock
Title:	Director
Qualifications:	BEng(Hons) CEng FICE MCIHT CMgr FCMI C.WEM MCIWEM

Revision History:

Rev	Date	Description	Prepared	Checked	Approved
01	April 2022	Issued for Planning	DS	MP	DS

This document has been prepared by Sutcliffe within the terms of the Contract with the Client to whom this document is addressed. Sutcliffe disclaims any responsibility to the Client and others in respect of matters outside the scope of the said contract. No person other than the Client shall rely on it in any respect and Sutcliffe shall owe no duty of care to any such third party.

Contents

1.0	Introduction
2.0	Existing flood risk
3.0	Drainage Hierarchy
3.1	Infiltration to ground
3.2	Discharge to water course
3.3	Discharge to surface water network
3.4	Discharge to combined sewer
4.0	Existing surface water drainage
5.0	Proposed surface water drainage
6.0	Climate Change
7.0	Discussion with Utility Company
8.0	Proposed surface water discharge rate
9.0	SuDS Interception
10.0	Water quality management
11.0	Proposed surface water drainage layout
12.0	Flood exceedance / drainage failure
13.0	Surface water drainage management and maintenance plan
Appendix A	Existing site layout Proposed site layout
Appendix B	Borehole logs
Appendix C	Infiltration test results
Appendix D	Existing drainage layout
Appendix E	Hydraulic calculations
Appendix F	Proposed Drainage Layout Drainage Areas Plan
Appendix G	Flood Exceedance
Appendix H	Correspondence

1.0 Site Description and Proposals

The site is currently void of development with the previous development having been demolished. The slab and access road are still present. The remainder of the site is covered with vegetation.

The total site area is approximately 1.03Ha

The site can be located by the following references.

Postcode M45 6DP

Coordinates 381195, 405724

Grid reference SD 81195 05724

A copy of the existing and proposed sites are included in Appendix A.

2.0 Existing Flood Risk

A site specific Flood Risk Assessment has been carried out and should be referred to for more information.

A summary from the FRA is.

- That the site is located within a Zone 1, very low risk flood area and the site is, therefore, considered not to be at risk of flooding from rivers or sea.
- That the site is indicated as having low risk surface water flooding with a water depth of below 300mm. The surface water flooding enters the site from the north west corner of the site and flows to the south east of the site.
- That the site is not at risk from flooding from reservoirs or other man-made water features

Therefore, from the above observations we confirm that the site has a low risk of flooding from surface water but no other sources.

3.0 Drainage Hierarchy

3.1 Infiltration to ground

Infiltration to ground is, in the main, provided by the provision of soakaways and permeable paving.

To provide infiltration via soakaways the ground conditions must be suitable to allow infiltration to occur and the ground water table must be at least 1.0m below the base of any soakaways provided.

To allow infiltration via permeable paving the ground conditions must be suitable to allow infiltration to occur.

Soakaways cannot be located within 5m of boundaries, highways or existing / proposed buildings.

The site has few areas that could accommodate soakaways, should infiltration be available.

3.1.1 Underlying geology

From the Phase 1 Preliminary Risk Assessment the superficial deposit is noted as Devensian Till (clay) and the solid geology is noted as being a mixture of mudstone, siltstone and sandstone across the site.

3.1.2 Intrusive ground investigation

From the Phase 2 Interpretative Ground Assessment the ground investigation logs record the ground as generally having a band of made ground to depths of between 1.0m and 2.4m below existing ground levels overlying silty / sandy clay becoming stiff with depth. The underlying rock was not encountered by any of the boreholes, which extended to a depth of 15.45m below existing ground levels.

A copy of the borehole logs are included in Appendix B.

3.1.3 British Geological Survey

A review of the BGS web site for logs in and around the proposed site, at the following web site address, [Borehole records - British Geological Survey \(bgs.ac.uk\)](http://bgs.ac.uk), was made and several boreholes were available to view, located approximately 200m to the west of the site.

All logs were viewed and it was apparent That they were all deep boreholes into the underlying rock and did not record the upper strata. One of the boreholes identifies rock at a depth of approximately 6m.

3.1.4 Infiltration Test

Two infiltration tests in accordance with BRE365 have been carried out and an infiltrate rate was not able to be calculated due to the nature of the ground.

There was no movement of water within the test pits.

The infiltration site notes are included in Appendix C.

3.2 **Discharge to a Water Course**

An inspection of historic / current maps and the Environment Agency maps reveal that there are no water courses located in the vicinity of the site.

3.3 **Discharge to surface water network**

A review of the existing drainage network within the surroundings of the development site was made and of United Utility sewer records. The review indicated that there are surface water sewers within reasonable distance of the site.

There are recorded surface water sewers located in both Oxbow Way, located to the south east of the site, and Brightwater Close, located to the east of the site.

There are no records available recording the depth or pipe diameters of the sewers but the surface water sewer located in Brightwater Close has been

identified as being suitable from the existing fall to the start of the sewer from the development site.

3.4 Discharge to combined sewer

A review of the existing drainage network and of United Utility sewer records within the surroundings of the development site was made and of United Utility sewer records.

The review indicated that there is a combined sewer located within the site.

A copy of the existing drainage drawings are included in Appendix D.

4.0 Existing site surface water drainage

There is currently no existing drainage on site.

The development previously occupying the site has been demolished.

A copy of the existing drainage network is included in Appendix D.

5.0 Proposed surface water drainage

The above discussion of the surface water drainage hierarchy has indicated that the proposed surface water drainage discharge point will be to the surface water sewer located in Brightwater Close. The surface water sewer located in Oxbow Way was investigated but proved to be too shallow to allow a connection from the development to

The reason for the above decision is based on the discussion of the drainage hierarchy. It has been proved that it is not possible to provide infiltration and there are no water courses or available surface water drainage networks within reasonable distance of the site.

The NPPF, paragraph 196, states that major developments should incorporate SuDS unless there is clear evidence that it would be inappropriate.

The below table lists the potential SuDS options and identifies whether the SuDS element is site appropriate and also provides a brief commentary as to its suitability for this development in relation to the site layout provided.

SuDS Option	Appropriate To Development	Comments
Soakaways	N	No infiltration rates were obtained for either of the infiltration tests carried out.
Infiltration basin	N	Not appropriate for this project.
Sand filter	N	Not appropriate for this project.

Filter strip	N	Not appropriate for this project.
Filter drains	N	Not appropriate for this project.
Detention basin	N	Not appropriate for this project.
Swales	N	Not appropriate for this project.
Rainwater harvesting / Rainwater Butts	P	RWH is a possibility for this site. Rainwater Butts are a possibility for this site
Green roofs	N	Green roofs are not appropriate for general housing where pitched roofs are provided.
Geo-cellular storage systems	P	These are a potential storage method and should be wrapped in geo membrane to retain the attenuated surface water.
Permeable pavements	P	Due to the nature of the site layout, proposed services to each house etc. it would not be practical to provide permeable paving to all plots but may be applicable to some plots. A lined system would be required as infiltration is not possible.
Ponds	N	Not appropriate for this project.
Oversized pipes	Y	These will be required to satisfy United Utilities as part of the proposed Section 104 Agreement that will be entered into to formally adopt the drainage located under the proposed adopted highway.
Tanks	P	A possible alternative to geo-cellular storage system, but generally more expensive, but may be required due to the location of required off line attenuation adjacent to the proposed highway.
Flow control devices	Y	Required to control off site discharge rates .

Where; Y: Suitable for use on a project of this size and nature
N: Not suitable for use on a project of this size and nature
P: Potentially suitable for use on a project of this size and nature

The following SuDS features have been identified as being potentially appropriate for this development.

The client has stated that rainwater harvesting is not appropriate for this development due to their high installation and maintenance costs that they are unable to recover from tenants as a social landlord. Rainwater butts are acceptable to the client.

Geo-cellular storage systems can be utilised as offline attenuation for storm events that are greater than 30 year events, up to the 100 year storm event including an allowance for climate change.

Permeable paving may be a potential option but will not be used as attenuation due to the S104 adoption requirements that all surface water attenuation is retained within the sewer network up to and including the 30 year storm event. Any additional storm attenuation greater than 30 year events will be difficult to attenuate to the site levels and no cost benefit would be achievable. Permeable paving will, however, provide benefit for interception and water quality and are discussed in later sections of this drainage strategy.

Oversized pipes will be used to accommodate the storm events up to and including the 30 year storm events as part of the Section 104 sewers.

Tanks may be required in lieu of geo-cellular attenuation and will depend on discussion with the Highway Authority in relation to the location of the required off line attenuation.

A flow control device will be required to reduce the surface water discharge from the site at green field runoff rates.

Therefore, from the above it is proposed to use a traditional drainage network with off line attenuation will be provided for this development. The client has stated that permeable paving is acceptable as a SuDS solution that can be incorporated into the drainage scheme.

6.0 Climate Change

From the DEFRA website the current peak rainfall allowances are provided.

Catchment peak river flow allowances are provided for the 2020's, 2050's and the 2080's.

The life span for residential housing is taken as 100 years, which puts the allowance for consideration of climate change into the 2080's

The following information is provided by the EA on the DEFRA web site.

Catchment:	Irwell Management Catchment
Central allowance:	35%
Higher allowance:	46%
Upper end allowance:	75%

The site is located in a zone 1 and the classification of the site use is 'More Vulnerable,' as categorised by the EA.

Therefore, in accordance with the DEFRA guidance we are required to consider the central allowance when carrying out hydraulic calculations for site drainage networks.

The higher allowance should be used when interrogating the site drainage networks for any affect that flooding may have on, or off, the development.

For this development the upper end allowance is only considered appropriate as a sensitivity test and will help assess the how sensitive the development is to climate

change and will ensure that the development is safe against large scale climate change over its lifetime.

7.0 Discussions with Utility Company

A pre-development enquiry was submitted to United Utilities and their response is included in Appendix H.

United Utilities have requested that any surface water connection to their network be to the existing surface water sewer in Brightwater Close.

As this connection will require access through 3rd party land we investigated a surface water discharge into Oxbow Way, where no 3rd party permissions would be required through privately owned land, but we were unable to achieve a suitable design.

8.0 Proposed surface water discharge rate

The site has been previously developed but has been demolished prior to this development.

The site is, therefore, classed as greenfield runoff as there is no current positive drainage network for the site.

The SuDS Manual, C753, and DEFRA Technical Standards direct the developer to discharge surface water at rates at greenfield runoff rates.

Greenfield runoff rates for the site have been calculated as being.

Q_{bar} : 6.4 l/s

Q_{1yr} : 5.6 l/s

Q_{2yr} : 6.0 l/s

Q_{30yr} : 10.9 l/s

Q_{100yr} : 13.4 l/s

The above greenfield runoff rates are reasonable to maintain throughout the life time of the development.

Therefore, it is reasonable to discharge surface water from the site at the Q_{bar} runoff rate of 6.4 l/s.

A copy of the greenfield calculation is included in Appendix F.

9.0 SuDS interception

The SuDS Manual, C753, seeks to intercept the first 5mm of rainfall. Interception is deemed to be delivered using one or a combination of the following.

- Rainwater harvesting / butts
- Infiltration

- Evapotranspiration using temporary shallow ponding or storage within the soil or upper aggregate layers

The below table lists the potential interception options and identifies whether the element is site appropriate and also provides a brief commentary as to its site suitability for this development in relation to the site layout provided.

Interception System	Interception methods that can be assumed to be compliant for zero runoff from the first 5mm rainfall for 80% of events during the summer and 50% in the winter	Comments for provision / non provision of interception system
Green Roof	All surfaces that have green roofs	Not appropriate for this project.
Rainwater harvesting system / Water butts	All surfaces drained to RWH systems designed to BS 8515:2009+A1 whether for surface water management or just water supply, provided the RWH design is based on regular daily demand for non-potable water	The client has stated that the use of a rain water harvesting tanks are not practical due to their high installation and maintenance costs, which would be borne by the housing association and not the occupier. The client stated that rainwater butts are acceptable to them.
Soakaway or other infiltration system	Areas of the site drained to systems that are designed to infiltrate runoff for events greater than a 1 month return period. Note: design of the infiltration system should be in accordance with C753 chapters 14 & 25	This is not possible for this site due to no infiltration via soakaways being possible.
Permeable pavements	All permeable pavements (lined or unlined) can be deemed to comply. Where the pavement also drains an adjacent impermeable area, compliance can be assumed when the permeable pavement is not lined. Refer to C753 for more details and description. Where the pavement also drains adjacent impermeable areas and is lined it is deemed not to comply	Permeable paving is a acceptable to the client where appropriate. The highway will not be permeable due to adoption requirements and services / sewers.
Filter strips / swales	Refer to C753 for compliance notes	Not appropriate for this project.
Infiltration trenches	Roads drained by infiltration trenches can be considered to provide interception	Not appropriate for this project.

Detention basins	Refer to C753 for compliance notes	Not appropriate for this project.
Bioretention area and rain water gardens	Refer to C753 for compliance notes	Not appropriate for this project.
Ponds	Areas drained by ponds that is maintained by the provision of an outlet structure are not deemed to intercept	Not appropriate for this project.

From the above table we have identified which interception systems may, or may not, be appropriate for this development.

The only form of potential interception is permeable paving to the private driveways. Some of the private driveways will not be suitable due to incoming services as listed in the above table. If permeable paving is provided then it would require to be lined due to infiltration not being available for this site.

10.0 Water quality management

Water quality needs to be considered in accordance with Section 26 of the SuDS manual.

We need to allocate suitable hazard indices (Table 26.2, C753) as follows.

Land Use	Pollution hazard level	Total suspended solids (TSS)	Metals	Hydro-carbons
Residential roofs	Very Low	0.2	0.2	0.05
Property drives	Low	0.5	0.4	0.4
Total Indices	N/A	0.7	0.6	0.45

We determine the pollution mitigation indices in accordance with Table 26.3, C753 as follows.

SuDS Component	Mitigation indices		
	Total Suspended Solids (TSS)	Metals	Hydrocarbons
Filter Strip	0.4	0.4	0.5
Filter drain	0.4	0.4	0.4
Swale	0.5	0.6	0.6
Bioretention system	0.8	0.8	0.8
Permeable pavement	0.7	0.6	0.7
Detention basin	0.5	0.5	0.6
Pond	0.7	0.7	0.5
Wetland	0.8	0.8	0.8
Proprietary treatment systems	These must demonstrate that they can address each of the contaminant types to acceptable levels for frequent events		

	up to approximately the 1 in 1 year return period event, for inflow concentrations relevant to the contributing drainage area.
--	--

From the above table there is only 1 appropriate options to provide water quality management, which is permeable paving. Permeable paving can be provided to all driveways.

From the tables above the total mitigation index is required to be greater than or equal to the pollution hazard index, as below table. (The table will require amending once the final solution has been specified). At this stage of design we cannot commit to a final solution as it will likely be finalised by the appointed principal contractor during the construction phase.

	Total suspended solids (TSS)	Metals	Hydro-carbons
Total hazard indices	0.7	0.6	0.45
Total mitigation indices	0.7	0.6	0.7

11.0 Proposed surface water drainage layout

From the above discussions and decision making processes the following surface water drainage network is proposed.

The maximum surface water discharge rate from the site will be set at 6.4 l/s in accordance with greenfield runoff rates and United Utilities requirements.

This discharge rate is reasonable and can be managed and maintained throughout the lifetime of the development.

From the above discussion and evidence we confirm that the proposed drainage layout will discharge into the existing surface water sewer located in Brightwater Close. The existing surface water sewer is a 225mm Ø. This is the surface water sewer that United Utilities have directed surface water discharge to.

The onsite drainage will consist of a piped drainage network in conjunction with an off line geo-cellular or concrete attenuation tank to manage surface water discharge from the site to a maximum rate of 6.4 l/s up to and including a 1 in 100 year storm event including an allowance of 35% for climate change. The drainage system will then be interrogated for a climate change of 46%.

A copy of the proposed preliminary drainage layout is included in Appendix F.

Hydraulic calculations have been carried out for the 1 year, 2 year, 30 year and 100 year + 35 & 46% climate change and a copy of the calculations are included in Appendix E.

A copy of the drainage areas plan indicating both permeable and impermeable areas is included in Appendix F.

12.0 Flood exceedance / Drainage failure / Sensitivity test

There is no flooding up to and including the 100 year storm event with an allowance of 35% for climate change and the discharge rate does not exceed 6.4 l/s.

In accordance with paragraph 167 (d) of the NPPF, we need to confirm that in the event of a drainage failure, or flood exceedance, event, that the development will remain safe and will not increase flood risk elsewhere and be safely managed.

The drainage network was interrogated using the higher allowance of 46%. The discharge rate did exceed 6.5 l/s, giving a discharge rate of 6.9 l/s, but no flooding was calculated.

A sensitivity test was carried out using the upper end allowance.

A flood flow analysis was carried out for the 100 year storm event with an allowance of 75% climate change for a 360 minute storm duration.

The results were saved and the output has been included on the flood exceedance drawing included in Appendix G.

Flooding was found to occur at two locations on the drainage network. The majority of flooding occurred at the low point of the drainage network and there was minor flooding at the off line attenuation. The flooding is seen to flow within the site with depths of flow ranging from less than 25mm to a maximum depth of 205mm.

Where there are vulnerable properties within a development, that cannot be relocated for whatever reason, it is necessary to incorporate appropriate flood resilience so that, in the event of a flood it can be brought back into use without significant refurbishment. This site does not have any vulnerable properties and there are no properties affected by flooding. All exceedance flooding is retained within the road or at low points around buildings

It can be seen from the exceedance / residual flooding drawing that there is safe access and egress in a flood event.

13.0 Management & Maintenance Plan

A Management & Maintenance Plan is required to ensure that the SuDS elements are maintained and managed to ensure they remain effective throughout the lifetime of the development.

Chapter 32 of The SuDS Manual, C753, provides information of maintenance requirements for SuDS systems.


This section of the drainage strategy will be developed in line with the end user so that they can have an input as to how it will be managed.

At this stage of the design process we would request a planning condition in relation to Management & Maintenance.

Appendix A

Existing Site Layout

Proposed Site Layout





Notes:

This drawing is the copyright Paddock Johnson Partnership Limited and may not be used without their prior written consent.
Written dimensions to be taken in preference to scaled dimensions.
Due to the inaccuracies of scanning, scanned images should not be scaled.

REV:	DATE:	DESCRIPTION:	BY:
A	15.7.21	Bungalows Added	PO
B	16.7.21	Areas Revised	PO
C	7.10.21	Drain Shown and Layout Adjusted	PO
D	1.11.21	Further landscaping shown	PO
E	23.11.21	Site Entrance Revised	PO
F	25.02.22	Parking shown for 31-37 Victoria Avenue	PO
G	1.3.22	Increased Road Radius Near Plot 17	PO
H	4.3.22	Revised Road Layout	PO
I	4.3.22	Pinch Point Increased	PO
J	11.3.22	Road widend at bends	PO
K	22.3.22	Parking outside 33 & 35 reinstated	PO

Unit Type Key

- 3B5P Houses
Type A
18 no. @ 84m2 (90% NDSS)
- 2B3P Walk Up Apartments
Type B
6 no. @ 55/63m2 (90% NDSS)
- 2B3P Bungalows
Type C
6 no. @ 55m2 (90% NDSS)

Total 30 no. units

CLIENT:

Onward Homes

PROJECT:

Former Wheatfields Day Care Centre
Victoria Avenue, Whitefield

DRAWING NUMBER:

21059-PJA-00-ZZ-DR-A-1000-K

DRAWING TITLE:

Proposed Site Plan

STATUS:

PLANNING

SCALE:1 : 500@A2

DATE:30.6.21

BY:PO


CHECKED:VA

PADDOCK
JOHNSON

Studio 2, The Lyceum,
Bath Street, Port Sunlight,
Merseyside, CH62 4UJ
0151 643 1234
admin@paddockjohnson.com
www.paddockjohnson.com
Paddock Johnson Partnership
Limited. Registered in England
and Wales. No. 06684275

Appendix B

Borehole Logs



Legend

Dynamic Sampling Borehole Locations (WS)

Dynamic Sampling Borehole Locations with Gas / Groundwater Installations (WS)

Trial Pit Locations (TP)

Trial Pit Locations with BRE 365 "Soakaway" Testing (TP / SA)

Plate Load Bearing Tests for California Bearing Ratio (CBR)

CO-ORDINATES

WS101 SD81170,05735	TP101 SD81186,05749
WS102 SD81196,05739	TP102 SD81167,05727
WS103 SD81208,05716	TP103/SA101 SD81222,05700
WS104 SD81202,05691	TP104/SA102 SD81181,05724
WS105 SD81195,05649	TP105 SD81203,05732
WS106 SD81184,05667	TP106 SD81214,05720
WS107 SD81177,05695	TP107 SD81198,05639
WS108 SD81210,05705	TP108 SD81215,05685
WS201 SD81147,05749	TP109 SD81170,05708
WS202 SD81160,05752	TP201 SD81161,05755
WS203 SD81155,05726	TP202 SD81169,05754
WS204 SD81172,05783	TP203 SD81154,05740
CBR101 SD81188,05743	
CBR102 SD81184,05727	
CBR103 SD81187,05689	
CBR104 SD81200,05670	

Structural & Civil Engineering
Geotechnical & Environmental Investigations
Building Surveying
Pre Planning Services

Liverpool Head Office:
0151 227 3155

Manchester Office:
0161 817 5180

North Wales Office:
01978 664 071

London Office:
020 8016 4320

www.sutcliffe.co.uk

Drawing Status

FOR INFORMATION

Client

ONWARD


Project

FORMER WHEATFIELD DAY CENTRE
WHITEFIELD

Drawing Title

SITE INVESTIGATION LOCATIONS
ON EXISTING PLAN (NORTHERN)

P01	PRELIMINARY DRAWING	06/22	DE	DB
Rev	Description	Date	By	Chkd
Date	Drawn By	Checked By		
JUNE 2022	D EVANS	D BOWEN		
Scale at A3 NTS		Project Number 31990LG		
Sheet Number 31990-SUT-ZZ-OO-DR-G-720-0001				Revision P01



CO-ORDINATES				
WS101	SD81170,05735	TP101	SD81186,05749	
WS102	SD81196,05739	TP102	SD81167,05727	
WS103	SD81208,05716	TP103/SA101	SD81222,05700	
WS104	SD81202,05691	TP104/SA102	SD81181,05724	
WS105	SD81195,05649	TP105	SD81203,05732	
WS106	SD81184,05667	TP106	SD81214,05720	
WS107	SD81177,05695	TP107	SD81198,05639	
WS108	SD81210,05705	TP108	SD81215,05685	
WS201	SD81147,05749	TP109	SD81170,05708	
WS202	SD81160,05752	TP201	SD81161,05755	
WS203	SD81155,05726	TP202	SD81169,05754	
WS204	SD81172,05783	TP203	SD81154,05740	
CBR101	SD81188,05743			
CBR102	SD81184,05727			
CBR103	SD81187,05689			
CBR104	SD81200,05670			



Structural & Civil Engineering
Geotechnical & Environmental Investigations
Building Surveying
Pre Planning Services

Liverpool Head Office:
0151 227 3155

Manchester Office:
0161 817 5180

North Wales Office:
01978 664 071

London Office:
020 8016 4320

www.sutcliffe.co.uk

RICS

HA

Alcumus

Constructionline

BSI

ISO 9001

ISO 14001

ISO 45001

Drawing Status

FOR INFORMATION

Client

ONWARD

Project

FORMER WHEATFIELD DAY CENTRE
WHITEFIELD



Drawing Title


SITE INVESTIGATION LOCATIONS
ON EXISTING PLAN (SOUTHERN)

P01	PRELIMINARY DRAWING	06/22	DE	DB
Rev	Description	Date	By	Chkd
Date	Drawn By	Checked By		
JUNE 2022	D EVANS	D BOWEN		
Scale at A3 NTS		Project Number 31990LG		
Sheet Number 31990-SUT-ZZ-OO-DR-G-720-0001				Revision P01

 Sutcliffe						Site Former Wheatfields Day Centre		Trial Pit Number TP201	
Excavation Method Trial Pit		Dimensions		Ground Level (mOD)		Client Onward		Job Number 31990LG	
		Location		Dates 26/05/2022		Engineer Michael Wiggins		Sheet 1/1	
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend	Water	
0.20-0.60	ES1				(0.20)	Vegetation over dark brown, sandy CLAY with roots (TOPSOIL).			
					0.20	Brown to light brown sandy CLAY. Sand is fine to medium.			
					(0.70)				
									
									
					0.90	Orange brown slightly sandy CLAY. Sand is fine.			
					(0.20)				
					1.10	Grey slightly silty sandy CLAY. Sand is fine.			
									
									
		(0.90)							
		2.00	Brown slightly sandy slightly gravelly CLAY with grey bands of organic material. Sand is fine. Gravel is fine angular to subrounded and of mixed lithologies.						
		(0.40)							
		2.40	Complete at 2.40m						
						Remarks			
						Trial pit dry			
						Scale (approx) 1:25		Logged By AT	



Client Onward	Job Number 31990LG
Engineer Michael Wiggins	Sheet 1/1

Description	Legend	Water
Vegetation over black, sandy CLAY. Sand is fine (TOPSOIL).		
Brown sandy gravelly CLAY. Sand is fine to medium. Gravel is fine, subangular and of mixed lithologies.		
Black clayey sandy PEAT. Sand is fine.		
Grey brown slightly silty slightly sandy CLAY. Sand is fine.		
Complete at 2.60m		





Scale (approx)	Logged By	Figure No.
1:25	AT	31990LG.TP202

Excavation Method Trial Pit	Dimensions	Ground Level (mOD)	Client Onward	Job Number 31990LG
	Location	Dates 26/05/2022	Engineer Michael Wiggins	Sheet 1/1

Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend	Water
					(0.40)	Vegetation over brown, sandy CLAY with roots (TOPSOIL).		
					0.40	Light brown slightly sandy slightly gravelly CLAY with grey bands. Sand is fine. Gravel is fine to medium, subangular and of mixed lithologies.		
					(1.60)			
					2.00	Complete at 2.00m		



Remarks Trial pit dry		
Scale (approx) 1:25	Logged By AT	Figure No. 31990LG.TP203

 Sutcliffe						Site Former Wheatfields Day Centre		Number WS201	
Excavation Method Drive-in Windowless Sampler		Dimensions		Ground Level (mOD)		Client Onward		Job Number 31990LG	
		Location		Dates 26/05/2022		Engineer Michael Wiggins		Sheet 1/1	
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description		Legend	Water
1.20-1.65	SPT N=6		1,0/0,2,2,2		(0.90)	Overgrown vegetation over dark brown grey, slightly sandy gravelly CLAY. Sand is fine. Gravel is fine to medium, subangular and of mixed lithologies. (TOPSOIL)			
					0.90	Soft light brown, slightly silty very sandy CLAY. Sand is fine.			
2.00-2.45	SPT N=12		3,3/3,3,3,3		(0.70)				
					1.60	Light brown, very clayey slightly silty, fine to medium grained SAND.			
2.00-2.45	SPT N=12		3,3/3,3,3,3		(0.30)				
					1.90	Stiff yellowish brown, very sandy gravelly CLAY. Sand is fine to medium. Gravel is fine, angular to subangular and of mixed lithologies.			
3.00-3.45	SPT N=15		3,5/3,4,4,4		(0.40)	Stiff brown slightly sandy gravelly CLAY with grey veining. Sand is fine. Gravel is fine to medium, angular to subangular and of mixed lithologies.			
					2.30				
4.00-4.45	SPT N=31		Water strike(1) at 4.00m, no rise after 20 mins. 4,4/5,8,8,10		(1.70)				
					4.00	Very stiff grey brown slightly sandy gravelly CLAY. Sand is fine to medium. Gravel is fine, angular to subangular and of mixed lithologies.			
5.00-5.45	SPT N=6		1,1/1,1,2,2		(0.90)				
					4.90	Medium dense grey brown slightly clayey fine to medium grained SAND with occasional coal fragments.			
					5.00				
					(0.45)	Loose grey brown fine to medium grained SAND.			
					5.45	Complete at 5.45m			
Remarks								Scale (approx)	Logged By
								1:50	AT
								Figure No. 31990LG.WS201	




Sutcliffe

Site Former Wheatfields Day Centre		Number WS202
Excavation Method Drive-in Windowless Sampler	Dimensions	Ground Level (mOD)
	Location	Dates 26/05/2022
		Client Onward
		Engineer Michael Wiggins
		Job Number 31990LG
		Sheet 1/1

Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend	Water
0.20-0.60	ES1				(0.90)	Grass over MADE GROUND: light brown slightly sandy slightly gravelly CLAY. Sand is fine. Gravel is fine to medium subangular and of brick.		
					0.90 (0.20) 1.10	Dark brown slightly clayey PEAT.		
1.20-1.65	SPT N=6		0,0/1,1,2,2			Stiff to very stiff brown slightly sandy gravelly CLAY. Sand is fine. Gravel is fine subangular and of mixed lithologies.		
2.00-2.45	SPT N=10		1,1/2,2,3,3		(2.30)			
3.00-3.45	SPT N=24		2,3/3,5,8,8		3.40	Stiff brown grey slightly sandy slightly gravelly CLAY. Sand is fine. Gravel is fine to medium subangular and of mixed lithologies.		
4.00-4.45	SPT N=7		2,2/1,2,2,2		4.00	Medium dense brown fine to medium grained SAND.		
					(1.00)			
5.00-5.45	SPT N=14		2,2/3,3,4,4		5.00	Very stiff brown very sandy CLAY. Sand is fine to medium.		
					(1.00)			
6.00-6.45	SPT N=21		3,3/4,5,5,7		6.00	Complete at 6.45m		

Remarks Borehole dry		Scale (approx) 1:50	Logged By AT
		Figure No. 31990LG.WS202	

 Sutcliffe					Site Former Wheatfields Day Centre		Number WS203		
Excavation Method Drive-in Windowless Sampler		Dimensions		Ground Level (mOD)		Client Onward		Job Number 31990LG	
		Location		Dates 26/05/2022		Engineer Michael Wiggins		Sheet 1/1	
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description		Legend	Water
1.20-1.65	SPT N=25		1,1/2,1,7,15		(0.40)	Vegetation over brown, slightly sandy, gravelly CLAY. Sand is fine. Gravel is fine to medium, subangular and of mixed lithologies. (TOPSOIL)			
					0.40	MADE GROUND: brown clayey fine to medium grained SAND.			
2.00-2.45	SPT N=13		2,2/4,3,3,3		(1.55)				
					1.95	MADE GROUND: black decomposing WOOD.			
					(0.20)				
					2.15	Stiff brown grey slightly silty slightly sandy CLAY. Sand is fine			
					(0.75)				
3.00-3.45	SPT N=11		2,2/2,3,3,3		2.90	Very stiff black grey slightly sandy CLAY. Sand is fine.			
					(1.10)				
4.00-4.45	SPT N=24		Water strike(1) at 4.00m, no rise after 20 mins. 3,4/5,6,6,7		4.00	Very stiff light brown very sandy CLAY. Sand is fine to medium.			▼1
					(1.00)				
5.00-5.45	SPT N=21		3,4/6,5,5,5		5.00	Medium dense grey brown clayey fine to medium grained SAND.			
					(1.00)				
					6.00	Complete at 6.45m			
Remarks								Scale (approx)	Logged By
								1:50	AT
								Figure No. 31990LG.WS203	

 Sutcliffe						Site Former Wheatfields Day Centre		Number WS204						
Excavation Method Drive-in Windowless Sampler		Dimensions		Ground Level (mOD)		Client Onward		Job Number 31990LG						
		Location		Dates 26/05/2022		Engineer Michael Wiggins		Sheet 1/1						
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend	Water						
0.20-0.50	ES1				(0.20)	Grass over dark brown, sandy CLAY with roots (TOPSOIL).								
					0.20	MADE GROUND: brown slightly sandy CLAY. Sand is fine.								
					(0.30)	MADE GROUND: black to dark brown sandy CLAY with organic material - possibly relic topsoil layer.								
					0.50	Stiff to very stiff brown slightly sandy CLAY. Sand is fine.								
1.20-1.65	SPT N=4		1,1/1,1,1,1		(0.20)	Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Sand is fine. Gravel is fine, subangular and of mixed lithologies.	                                              							
					(0.70)									
					2.00-2.45			SPT N=13		2,2/3,3,3,4		(2.10)		
3.00-3.45	SPT N=12		2,3/3,4,3,2		3.10	Very stiff brown friable very sandy gravelly CLAY. Sand is fine	                                              							
					(0.90)									
4.00-4.45	SPT(C) N=38		10,11/13,12,6,7		4.00	Complete at 6.02m								
4.45-4.90	SPT(C) N=20		5,4/4,4,7,5											
4.90-5.35	SPT(C) N=22		7,6/6,5,5,6											
5.35-5.80	SPT(C) N=43		9,10/11,9,11,12											
5.80-6.02	SPT(C) 38/70		/13,13,12											
Remarks Driving cobble from 3.00m to 4.00m - continued with CPT to 6.02m							Scale (approx) 1:50	Logged By AT						
							Figure No. 31990LG.WS204							

Appendix C

Infiltration Test Results



Sutcliffe Soakaway Test Field Record Sheet

Site: Former Wheatfields Day Centre, Whitefield

Client: Onward

Job No.: 31990LG

Infiltration Pit: TP103(SA)

Test No: 1

Start Time: 10:00

Date: 20/9/2021

Pit Dimensions (m)

Length: 1.7 Width: 0.6

Depth: 2.3

Time (mins)	Depth (m)
0	0.85
30	0.85
60	0.85
230	0.85

Time (mins)	Depth (m)

Start Depth	0.85
Effective 75% depth	1.2125
Effective 50% depth	1.575
Effective 25% depth	1.9375

Elapsed Time N/A

Elapsed Time N/A

Please Print Me Double Sided to Save Paper!

Sketch Pit Dimensions

Comments:



Sutcliffe Soakaway Test Field Record Sheet

Site: Former Wheatfields Day Centre, Whitefield

Client: Onward

Job No.: 31990LG

Infiltration Pit: TP104 (SA)

Test No: 1

Start Time: 10:50

Date: 20/09/2021

Pit Dimensions (m)

Length: 1.8 Width: 0.6

Depth: 2.15

Time (mins)	Depth (m)
0	1.1
30	1.1
60	1.1
230	1.1

Time (mins)	Depth (m)

Start Depth	1.1
Effective 75% depth	1.3625
Effective 50% depth	1.625
Effective 25% depth	1.8875

Elapsed Time N/A

Elapsed Time N/A

Please Print Me Double Sided to Save Paper!

Sketch Pit Dimensions

Comments:

Appendix D

Existing Drainage Layout

Appendix E

Qbar Hydraulic Calculations

Proposed Drainage Network Hydraulic Calculations

Sutcliffe		Page 1																												
18-20 Harrington Street Liverpool L2 9QA	Wheatfield Day Centre Whitefield Manchester																													
Date 16/06/2022 15:46 File 31990_Qbar.SRCX	Designed by DS Checked by																													
Innovyze	Source Control 2020.1.3																													
<u>ICP SUDS Mean Annual Flood</u> Input <table><tr><td>Return Period (years)</td><td>2</td><td>Soil</td><td>0.450</td></tr><tr><td>Area (ha)</td><td>1.000</td><td>Urban</td><td>0.000</td></tr><tr><td>SAAR (mm)</td><td>970</td><td>Region Number</td><td>Region 10</td></tr></table> Results 1/s <table><tr><td>QBAR Rural</td><td>6.4</td></tr><tr><td>QBAR Urban</td><td>6.4</td></tr><tr><td colspan="2"> </td></tr><tr><td>Q2 years</td><td>6.0</td></tr><tr><td colspan="2"> </td></tr><tr><td>Q1 year</td><td>5.6</td></tr><tr><td>Q30 years</td><td>10.9</td></tr><tr><td>Q100 years</td><td>13.4</td></tr></table>			Return Period (years)	2	Soil	0.450	Area (ha)	1.000	Urban	0.000	SAAR (mm)	970	Region Number	Region 10	QBAR Rural	6.4	QBAR Urban	6.4			Q2 years	6.0			Q1 year	5.6	Q30 years	10.9	Q100 years	13.4
Return Period (years)	2	Soil	0.450																											
Area (ha)	1.000	Urban	0.000																											
SAAR (mm)	970	Region Number	Region 10																											
QBAR Rural	6.4																													
QBAR Urban	6.4																													
Q2 years	6.0																													
Q1 year	5.6																													
Q30 years	10.9																													
Q100 years	13.4																													
©1982-2020 Innovyze																														

Sutcliffe		Page 0
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:31 File 31990-MODEL 003b.mdx	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Pipe Sizes STANDARD Manhole Sizes STANDARD

Designed with Level Soffits

« - Indicates pipe capacity < flow

Network Results Table

Sutcliffe		Page 1
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:31 File 31990-MODEL 003b.mdx	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

Network Design Table for Surface Network 1

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
3.001	6.037	0.060	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.005	10.331	0.248	41.7	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.006	24.556	0.246	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.007	21.852	0.219	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.008	19.202	0.192	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.009	11.229	0.112	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
3.001	50.00	5.14	92.260	0.000	0.0	0.0	0.0	1.00	17.8	0.0
1.005	50.00	6.13	92.200	0.468	0.0	0.0	0.0	1.56	27.6«	63.4
1.006	50.00	6.54	91.754	0.468	0.0	0.0	0.0	1.00	17.8«	63.4
1.007	50.00	6.90	91.509	0.468	0.0	0.0	0.0	1.00	17.8«	63.4
1.008	50.00	7.22	91.290	0.468	0.0	0.0	0.0	1.00	17.8«	63.4
1.009	50.00	7.40	91.098	0.468	0.0	0.0	0.0	1.00	17.8«	63.4

Sutcliffe		Page 2
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:31 File 31990-MODEL 003b.mdx	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

Area Summary for Surface Network 1

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	User	-	100	0.058	0.058	0.058
	User	-	100	0.005	0.005	0.063
	User	-	100	0.010	0.010	0.073
1.001	-	-	100	0.000	0.000	0.000
1.002	User	-	100	0.016	0.016	0.016
1.003	User	-	100	0.032	0.032	0.032
	User	-	100	0.017	0.017	0.049
	User	-	100	0.017	0.017	0.067
	User	-	100	0.002	0.002	0.069
1.004	User	-	100	0.021	0.021	0.021
	User	-	100	0.016	0.016	0.037
	User	-	100	0.016	0.016	0.053
	User	-	100	0.013	0.013	0.066
	User	-	100	0.016	0.016	0.082
	User	-	100	0.002	0.002	0.084
2.000	User	-	100	0.022	0.022	0.022
	User	-	100	0.028	0.028	0.050
	User	-	100	0.025	0.025	0.075
2.001	User	-	100	0.033	0.033	0.033
2.002	User	-	100	0.015	0.015	0.015
	User	-	100	0.016	0.016	0.031
	User	-	100	0.023	0.023	0.054
	User	-	100	0.017	0.017	0.071
	User	-	100	0.042	0.042	0.113
	User	-	100	0.005	0.005	0.117
3.000	-	-	100	0.000	0.000	0.000
3.001	-	-	100	0.000	0.000	0.000
1.005	-	-	100	0.000	0.000	0.000
1.006	-	-	100	0.000	0.000	0.000
1.007	-	-	100	0.000	0.000	0.000
1.008	-	-	100	0.000	0.000	0.000
1.009	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				0.468	0.468	0.468

Free Flowing Outfall Details for Surface Network 1

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.009	EXMH 2710	92.336	90.986	0.000	1500	0

Sutcliffe		Page 3
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:31 File 31990-MODEL 003b.mdx	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

Simulation Criteria for Surface Network 1

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	0.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	2	Number of Time/Area Diagrams	0
Number of Offline Controls	1	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	2	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.000	Storm Duration (mins)	30
Ratio R	0.328		

©1982-2020 Innovyze

Sutcliffe		Page 4																																																																																																													
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester																																																																																																														
Date 04/07/2022 13:31 File 31990-MODEL 003b.mdx	Designed by DS Checked by																																																																																																														
Innovyze	Network 2020.1.3																																																																																																														
<u>Online Controls for Surface Network 1</u> <u>Non Return Valve Manhole: MH2, DS/PN: 3.001, Volume (m³): 3.6</u> <u>Hydro-Brake® Optimum Manhole: S12, DS/PN: 1.005, Volume (m³): 36.8</u> <table><tr><td>Unit Reference</td><td>MD-SHE-0107-6400-1800-6400</td></tr><tr><td>Design Head (m)</td><td>1.800</td></tr><tr><td>Design Flow (l/s)</td><td>6.4</td></tr><tr><td>Flush-Flo™</td><td>Calculated</td></tr><tr><td>Objective</td><td>Minimise upstream storage</td></tr><tr><td>Application</td><td>Surface</td></tr><tr><td>Sump Available</td><td>Yes</td></tr><tr><td>Diameter (mm)</td><td>107</td></tr><tr><td>Invert Level (m)</td><td>92.200</td></tr><tr><td>Minimum Outlet Pipe Diameter (mm)</td><td>150</td></tr><tr><td>Suggested Manhole Diameter (mm)</td><td>1200</td></tr></table> <table><tr><th>Control Points</th><th>Head (m)</th><th>Flow (l/s)</th></tr><tr><td>Design Point (Calculated)</td><td>1.800</td><td>6.4</td></tr><tr><td>Flush-Flo™</td><td>0.466</td><td>6.0</td></tr><tr><td>Kick-Flo®</td><td>0.953</td><td>4.8</td></tr><tr><td>Mean Flow over Head Range</td><td>-</td><td>5.4</td></tr></table> The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated <table><tr><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th></tr><tr><td>0.100</td><td>3.6</td><td>1.200</td><td>5.3</td><td>3.000</td><td>8.1</td><td>7.000</td><td>12.2</td></tr><tr><td>0.200</td><td>5.3</td><td>1.400</td><td>5.7</td><td>3.500</td><td>8.7</td><td>7.500</td><td>12.6</td></tr><tr><td>0.300</td><td>5.8</td><td>1.600</td><td>6.1</td><td>4.000</td><td>9.3</td><td>8.000</td><td>13.0</td></tr><tr><td>0.400</td><td>6.0</td><td>1.800</td><td>6.4</td><td>4.500</td><td>9.9</td><td>8.500</td><td>13.3</td></tr><tr><td>0.500</td><td>6.0</td><td>2.000</td><td>6.7</td><td>5.000</td><td>10.4</td><td>9.000</td><td>13.7</td></tr><tr><td>0.600</td><td>5.9</td><td>2.200</td><td>7.0</td><td>5.500</td><td>10.8</td><td>9.500</td><td>14.1</td></tr><tr><td>0.800</td><td>5.5</td><td>2.400</td><td>7.3</td><td>6.000</td><td>11.3</td><td></td><td></td></tr><tr><td>1.000</td><td>4.9</td><td>2.600</td><td>7.6</td><td>6.500</td><td>11.7</td><td></td><td></td></tr></table>			Unit Reference	MD-SHE-0107-6400-1800-6400	Design Head (m)	1.800	Design Flow (l/s)	6.4	Flush-Flo™	Calculated	Objective	Minimise upstream storage	Application	Surface	Sump Available	Yes	Diameter (mm)	107	Invert Level (m)	92.200	Minimum Outlet Pipe Diameter (mm)	150	Suggested Manhole Diameter (mm)	1200	Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	1.800	6.4	Flush-Flo™	0.466	6.0	Kick-Flo®	0.953	4.8	Mean Flow over Head Range	-	5.4	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	3.6	1.200	5.3	3.000	8.1	7.000	12.2	0.200	5.3	1.400	5.7	3.500	8.7	7.500	12.6	0.300	5.8	1.600	6.1	4.000	9.3	8.000	13.0	0.400	6.0	1.800	6.4	4.500	9.9	8.500	13.3	0.500	6.0	2.000	6.7	5.000	10.4	9.000	13.7	0.600	5.9	2.200	7.0	5.500	10.8	9.500	14.1	0.800	5.5	2.400	7.3	6.000	11.3			1.000	4.9	2.600	7.6	6.500	11.7		
Unit Reference	MD-SHE-0107-6400-1800-6400																																																																																																														
Design Head (m)	1.800																																																																																																														
Design Flow (l/s)	6.4																																																																																																														
Flush-Flo™	Calculated																																																																																																														
Objective	Minimise upstream storage																																																																																																														
Application	Surface																																																																																																														
Sump Available	Yes																																																																																																														
Diameter (mm)	107																																																																																																														
Invert Level (m)	92.200																																																																																																														
Minimum Outlet Pipe Diameter (mm)	150																																																																																																														
Suggested Manhole Diameter (mm)	1200																																																																																																														
Control Points	Head (m)	Flow (l/s)																																																																																																													
Design Point (Calculated)	1.800	6.4																																																																																																													
Flush-Flo™	0.466	6.0																																																																																																													
Kick-Flo®	0.953	4.8																																																																																																													
Mean Flow over Head Range	-	5.4																																																																																																													
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																																																								
0.100	3.6	1.200	5.3	3.000	8.1	7.000	12.2																																																																																																								
0.200	5.3	1.400	5.7	3.500	8.7	7.500	12.6																																																																																																								
0.300	5.8	1.600	6.1	4.000	9.3	8.000	13.0																																																																																																								
0.400	6.0	1.800	6.4	4.500	9.9	8.500	13.3																																																																																																								
0.500	6.0	2.000	6.7	5.000	10.4	9.000	13.7																																																																																																								
0.600	5.9	2.200	7.0	5.500	10.8	9.500	14.1																																																																																																								
0.800	5.5	2.400	7.3	6.000	11.3																																																																																																										
1.000	4.9	2.600	7.6	6.500	11.7																																																																																																										
©1982-2020 Innovyze																																																																																																															

Sutcliffe		Page 6												
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester													
Date 04/07/2022 13:31 File 31990-MODEL 003b.mdx	Designed by DS Checked by													
Innovyze	Network 2020.1.3													
<u>Storage Structures for Surface Network 1</u> <u>Tank or Pond Manhole: MH1 , DS/PN: 3.000</u> Invert Level (m) 92.299 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>112.0</td><td>1.600</td><td>112.0</td><td>1.601</td><td>0.0</td></tr></table>			Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	112.0	1.600	112.0	1.601	0.0
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)									
0.000	112.0	1.600	112.0	1.601	0.0									
©1982-2020 Innovyze														

Sutcliffe		Page 0	
18-20 Harrington Street Liverpool L2 9QA		Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:32 File 31990-MODEL 003b.mdx		Designed by DS Checked by	
Innovyze		Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 0.000

Hot Start Level (mm) 0

Inlet Coefficient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 1

Number of Online Controls 2

Number of Time/Area Diagrams 0

Number of Offline Controls 1

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR

Ratio R 0.328

Region England and Wales Cv (Summer) 1.000

M5-60 (mm) 19.000 Cv (Winter) 1.000

Margin for Flood Risk Warning (mm) 300.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS Status ON

DVD Status OFF

Inertia Status OFF

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440

Return Period(s) (years) 1

Climate Change (%) 0

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	S1	120 Summer	1	+0%					92.689
1.001	S2	120 Summer	1	+0%					92.689
1.002	S3	120 Summer	1	+0%					92.689
1.003	S4	120 Summer	1	+0%					92.690
1.004	S6	120 Summer	1	+0%					92.690
2.000	S9	120 Summer	1	+0%					92.690
2.001	S10	120 Summer	1	+0%					92.690
2.002	S11	120 Summer	1	+0%					92.690
3.000	MH1	15 Summer	1	+0%					92.298
3.001	MH2	15 Summer	1	+0%					92.260
1.005	S12	120 Summer	1	+0%	1/15 Summer			0	92.690
1.006	S13	360 Winter	1	+0%					91.816
1.007	S14	240 Summer	1	+0%					91.570
1.008	S15	360 Winter	1	+0%					91.352
1.009	S16	360 Winter	1	+0%					91.161

©1982-2020 Innovyze

Sutcliffe		Page 0
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:33 File 31990-MODEL 003b.mdx	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

Simulation Criteria

Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	2	Number of Time/Area Diagrams	0
Number of Offline Controls	1	Number of Real Time Controls	0

Rainfall Model	FSR	Ratio R	0.328
Region	England and Wales	Cv (Summer)	1.000
M5-60 (mm)	19.000	Cv (Winter)	1.000

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2
Climate Change (%)	0

Sutcliffe

18-20 Harrington Street
Liverpool
L2 9QA

Date 04/07/2022 13:34
File 31990-MODEL 003b.mdx

Innovyze

Former Wheatfields Day Centre
Whitefield
Manchester

Designed by DS
Checked by

Network 2020.1.3

Page 0



Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 0.000

Hot Start Level (mm) 0

Inlet Coefficient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 1

Number of Online Controls 2

Number of Time/Area Diagrams 0

Number of Offline Controls 1

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model

FSR

Ratio R 0.328

Region England and Wales Cv (Summer) 1.000

M5-60 (mm)

19.000 Cv (Winter) 1.000

Margin for Flood Risk Warning (mm)

300.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS Status

ON

DVD Status

OFF

Inertia Status

OFF

Profile(s)

Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440

Return Period(s) (years)

30

Climate Change (%)

0

	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level
1.000	S1	240 Winter	30	+0%	30/120 Summer				93.809
1.001	S2	240 Winter	30	+0%	30/60 Summer				93.809
1.002	S3	240 Winter	30	+0%	30/60 Summer				93.809
1.003	S4	240 Winter	30	+0%	30/60 Summer				93.809
1.004	S6	240 Winter	30	+0%	30/60 Summer				93.809
2.000	S9	240 Winter	30	+0%	30/60 Summer				93.809
2.001	S10	240 Winter	30	+0%	30/60 Summer				93.809
2.002	S11	240 Winter	30	+0%	30/60 Summer				93.809
3.000	MH1	15 Summer	30	+0%					92.298
3.001	MH2	15 Summer	30	+0%					92.260
1.005	S12	240 Winter	30	+0%	30/15 Summer			0	93.809
1.006	S13	240 Winter	30	+0%					91.816
1.007	S14	240 Winter	30	+0%					91.571
1.008	S15	240 Winter	30	+0%					91.353
1.009	S16	240 Winter	30	+0%					91.162

©1982-2020 Innovyze

Sutcliffe		Page 1
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:34 File 31990-MODEL 003b.mdx	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

PN	US/MH Name	Surcharged		Flooded		Flow / Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow	Cap.					
1.000	S1	0.470	0.000	0.01				5.0	SURCHARGED	
1.001	S2	0.512	0.000	0.00				2.4	SURCHARGED	
1.002	S3	0.528	0.000	0.01				3.2	SURCHARGED	
1.003	S4	0.570	0.000	0.01				3.8	SURCHARGED	
1.004	S6	0.654	0.000	0.01				4.5	SURCHARGED	
2.000	S9	0.563	0.000	0.01				5.5	SURCHARGED	
2.001	S10	0.600	0.000	0.01				5.0	SURCHARGED	
2.002	S11	0.675	0.000	0.02				8.5	SURCHARGED	
3.000	MH1	-0.300	0.000	0.00				0.0	OK	
3.001	MH2	-0.150	0.000	0.00				0.0	OK	
1.005	S12	1.459	0.000	0.25		0.0		6.1	SURCHARGED	
1.006	S13	-0.088	0.000	0.36				6.1	OK	
1.007	S14	-0.088	0.000	0.36				6.1	OK	
1.008	S15	-0.088	0.000	0.36				6.1	OK	
1.009	S16	-0.086	0.000	0.38				6.1	OK	

Sutcliffe		Page 1
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:35 File 31990-MODEL 003b_100 yr...	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

PN	US/MH Name	Water	Surcharged	Flooded	Flow / Overflow Cap. (l/s)		Half Drain	Pipe	Status
		Level (m)	Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)	
1.000	S1	94.061	0.722	0.000	0.05	133.1	27.3	SURCHARGED	
1.001	S2	94.059	0.763	0.000	0.05		23.6	SURCHARGED	
1.002	S3	94.058	0.778	0.000	0.05		28.1	SURCHARGED	
1.003	S4	94.056	0.817	0.000	0.06		47.2	SURCHARGED	
1.004	S6	94.052	0.896	0.000	0.10		70.2	SURCHARGED	
2.000	S9	94.056	0.810	0.000	0.06		31.6	SURCHARGED	
2.001	S10	94.054	0.845	0.000	0.05		36.6	FLOOD RISK	
2.002	S11	94.051	0.917	0.000	0.14		74.2	SURCHARGED	
3.000	MH1	93.626	1.028	0.000	0.13		8.2	SURCHARGED	
3.001	MH2	93.714	1.304	0.000	0.40	6.0	SURCHARGED		
1.005	S12	94.046	1.696	0.000	0.26	6.5	SURCHARGED		
1.006	S13	91.818	-0.086	0.000	0.38	6.5	OK		
1.007	S14	91.573	-0.086	0.000	0.39	6.5	OK		
1.008	S15	91.355	-0.085	0.000	0.39	6.5	OK		
1.009	S16	91.164	-0.084	0.000	0.40	6.5	OK		

PN	US/MH Level	
	Name	Exceeded
1.000	S1	
1.001	S2	
1.002	S3	
1.003	S4	
1.004	S6	
2.000	S9	
2.001	S10	
2.002	S11	
3.000	MH1	
3.001	MH2	
1.005	S12	
1.006	S13	
1.007	S14	
1.008	S15	
1.009	S16	

Sutcliffe		Page 1
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 13:37 File 31990-MODEL 003b_100 yr...	Designed by DS Checked by	
Innovyze	Network 2020.1.3	


Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

PN	US/MH Name	Water	Surcharged	Flooded	Flow / Overflow		Half Drain	Pipe	Status
		Level (m)	Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)	
1.000	S1	94.096	0.757	0.000	0.05			30.5	SURCHARGED
1.001	S2	94.094	0.797	0.000	0.06			29.1	SURCHARGED
1.002	S3	94.092	0.812	0.000	0.06			34.3	SURCHARGED
1.003	S4	94.090	0.851	0.000	0.08			57.7	SURCHARGED
1.004	S6	94.085	0.929	0.000	0.13			85.8	SURCHARGED
2.000	S9	94.090	0.844	0.000	0.06			33.3	SURCHARGED
2.001	S10	94.088	0.878	0.000	0.06			44.1	FLOOD RISK
2.002	S11	94.084	0.949	0.000	0.18			90.7	SURCHARGED
3.000	MH1	93.892	1.294	0.000	0.20			12.0	SURCHARGED
3.001	MH2	93.959	1.549	0.000	0.69			10.3	SURCHARGED
1.005	S12	94.078	1.728	0.000	0.26	165.6		6.5	SURCHARGED
1.006	S13	91.819	-0.086	0.000	0.39			6.5	OK
1.007	S14	91.573	-0.085	0.000	0.39			6.5	OK
1.008	S15	91.355	-0.085	0.000	0.39			6.5	OK
1.009	S16	91.165	-0.084	0.000	0.41			6.5	OK

PN	US/MH Level	
	Name	Exceeded
1.000	S1	
1.001	S2	
1.002	S3	
1.003	S4	
1.004	S6	
2.000	S9	
2.001	S10	
2.002	S11	
3.000	MH1	
3.001	MH2	
1.005	S12	
1.006	S13	
1.007	S14	
1.008	S15	
1.009	S16	

Appendix F

Proposed Drainage Layout Drainage Areas Plan



GENERAL NOTES

- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT STRUCTURAL AND ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS TO BE CHECKED ON SITE BY THE CONTRACTOR / FABRICATOR PRIOR TO COMMENCEMENT OF WORKS.
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED OTHERWISE.
- ALL WORKS TO BE CARRIED OUT IN STRICT ACCORDANCE WITH THE ENGINEER'S SPECIFICATIONS, RELEVANT BRITISH STANDARDS AND WHERE APPLICABLE LOCAL AUTHORITIES REQUIREMENTS.

DRAINAGE KEY

- SITE BOUNDARY
- SURFACE WATER SEWER / MH
- FOUL WATER SEWER / MH
- COMBINED WATER SEWER / MH
- PRIVATE SURFACE WATER SEWER / MH
- PRIVATE FOUL WATER SEWER / MH
- SEWER EASEMENT (AS DIMENSIONED)
- EXISTING SURFACE WATER SEWER / MH
- EXISTING FOUL WATER SEWER / MH
- RWP = Rainwater pipe location
- SP = Soil pipe location
- Permeable driveway
- Surface Water Attenuation Cells

NOTE: ALL RWP/SP/BIG POSITIONS TO BE CONFIRMED BY ARCHITECT PRIOR TO START OF WORKS ON SITE

P03	PRIVATE DRAINAGE ADDED	30.06.22	AJB	DS
P02	SITE PLAN UPDATED	23.03.22	MJD	DS
P01	PRELIMINARY ISSUE	11.11.21	JG	DS
Rev	Description	Date	By	Chkd

Drawing Status

PRELIMINARY DRAWING

Sutcliffe

Client
ONWARD

Project
FORMER WHEATFIELDS DAY CENTRE WHITEFIELD

Drawing Title
INDICATIVE DRAINAGE LAYOUT

Date NOV. 2021	Drawn By JG	Checked By DS
Scale at A1 1:250	Project Number 31990	Revision P03

Sheet Number
31990-SUT-ZZ-XX-DR-C-6020





Structural & Civil Engineering
Geotechnical & Environmental Investigations
Building Surveying
Pre Planning Services

Liverpool Head Office: 0151 227 3155
Manchester Office: 0161 817 5180
North Wales Office: 01978 664 073
London Office: 020 8016 4320

www.sutcliffe.co.uk



Drawing Status

PRELIMINARY

Client

ONWARD

Project

**FORMER WHEATFIELDS FAY CENTRE
WHITEFIELD**

Drawing Title

DRAINED AREAS PLAN

P01	ISSUED FOR COMMENT	29.06.22	AJB	DS
Rev	Description	Date	By	Chkd
Date	Drawn By	Checked By		
JULY 2022	AJB	DS		
Scale at A3 1:500		Project Number 31990		
Sheet Number 31990-SUT-ZZ-XX-DR-C-6003				Revision P01

Appendix G

Flood Exceedance


Sutcliffe		Page 0
18-20 Harrington Street Liverpool L2 9QA	Former Wheatfields Day Centre Whitefield Manchester	
Date 04/07/2022 14:24 File 31990-MODEL 003b_Flood ...	Designed by DS Checked by	
Innovyze	Network 2020.1.3	

Summary of Results for 360 minute 100 year Winter (Surface Network 1)

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF
 Analysis Timestep Fine Inertia Status OFF
 DTS Status ON

WARNING: The analysis maybe unstable. Please see the method of analysis help for more details.

		Water	Surcharged	Flooded			Half Drain	Pipe	
	US/MH	Level	Depth	Volume	Flow /	Overflow	Time	Flow	
PN	Name	(m)	(m)	(m³)	Cap.	(l/s)	(mins)	(l/s)	Status
1.000	S1	94.203	0.864	0.000	0.01			8.1	SURCHARGED
1.001	S2	94.199	0.902	0.000	0.02			8.1	SURCHARGED
1.002	S3	94.198	0.918	0.000	0.02			9.8	SURCHARGED
1.003	S4	94.203	0.964	0.000	0.02			17.5	SURCHARGED
1.004	S6	94.218	1.062	0.000	0.04			26.8	SURCHARGED
2.000	S9	94.197	0.951	0.000	0.02			8.3	SURCHARGED
2.001	S10	94.202	0.992	96.479	0.02			12.0	FLOOD
2.002	S11	94.222	1.087	0.000	0.05			25.0	SURCHARGED
3.000	MH1	94.509	1.911	0.000	0.70			42.7	SURCHARGED
3.001	MH2	95.116	2.706	1.991	1.80			26.7	FLOOD
1.005	S12	94.230	1.880	0.000	0.27	54.5		6.6	SURCHARGED
1.006	S13	91.820	-0.084	0.000	0.39			6.6	OK
1.007	S14	91.574	-0.084	0.000	0.39			6.6	OK
1.008	S15	91.356	-0.084	0.000	0.40			6.6	OK
1.009	S16	91.166	-0.083	0.000	0.41			6.6	OK



 Sutcliffe Structural & Civil Engineering Geotechnical & Environmental Investigations Building Surveying Pre Planning Services Liverpool Head Office: 0151 227 3155 Manchester Office: 0161 817 5180 North Wales Office: 01978 664 071 London Office: 020 8016 4320 www.sutcliffe.co.uk Drawing Status PRELIMINARY DRAWING	Client ONWARD Project FORMER WHEATFIELDS DAY CENTRE WHITEFIELDS	Drawing Title FLOOD EXCEEDANCE DRAWING	Rev Issued For Comment Date 20.06.22 By AJB Chkd DS Date JUNE 2022 Drawn By AJB Checked By DS Scale at A3 1:500 Project Number 31990 Sheet Number 31990-SUT-ZZ-XX-DR-C-6002 Revision P01
--	---	--	---

Appendix H

Correspondence

From: [Wastewater Developer Services](#)
To: [Dave Samuels](#)
Cc: [Wastewater Developer Services](#)
Subject: Pre Development Enquiry for: Former Wheatfields Day Centre M45 8SG UU Reference Number : 4200045674
Date: 16 December 2021 12:08:28
Attachments: [image001.png](#)

Good Afternoon Dave,

Pre Development Enquiry for: Former Wheatfields Day Centre M45 8SG **UU**
Reference Number : 4200045674

-

We have carried out an assessment of your application which is based on the information provided. This pre-development advice on your drainage strategy will be valid for 12 months. Your drainage strategy will need to be reviewed by other competent authorities as part of the planning process, and we advise that you carry out the necessary site investigations to confirm the viability of your proposals.

If your investigations require access to our public sewer network, we ask that you contact our network engineers with a request for an access certificate via our main contact telephone number 0345 3723223 or refer to the link below:

<https://www.unitedutilities.com/builders-developers/working-near-our-assets/>

Foul Water

Foul flow from this site will be allowed to drain into the public foul water/combined sewer system.

Our preferred point of discharge would be to the 600mm diameter public combined sewer within your proposed development at an unrestricted rate
Please ensure any proposed connections are not against the flow

If you are able to identify an alternative, more suitable point of discharge, we request that you contact us at your earliest convenience so that we can assess suitability.

Surface Water

All surface water flow from the proposed development should drain in-line with the drainage hierarchy, as outlined in Paragraph 80, (Reference ID: 7-080-20150323), of the National Planning Practice Guidance. We also recommend you prioritise the use of multi-functional sustainable drainage systems for the management of surface water in accordance with national planning policy.

Generally, the aim should be to discharge surface run off as high up the following hierarchy of drainage options as reasonably practicable.

This is outlined as follows, in order of priority:

1. **into the ground (infiltration);**
2. **to a surface waterbody;**
3. **to a surface water sewer or highway drain;**
4. **to a combined sewer.**

For guidance, The **North West SuDS Pro-Forma** provides information on the appropriate evidence required at each stage of the hierarchy, to demonstrate how each level has been discounted.

The Lead Local Flood Authority has responsibility for all surface water drainage concerns and their input to your proposal is critical. You should also consider whether it is necessary to discuss your proposal with the Environment Agency, or Internal Drainage Board (if operating in your area).

The Local Planning Authority are the determining authority for any application for planning permission and the appropriate authority for determining cost viability of a proposed drainage scheme, such assessments are outside of the jurisdiction of United Utilities.

Infiltration

Surface water runoff generated from this development should discharge to the ground via infiltration system where feasible.

A detailed evidence based feasibility assessment must be carried out in line with Chapter 25 of the CIRIA SuDS Manual 2015 to determine whether infiltration is a suitable method of surface water disposal.

Particular attention must be paid to Ground Water Source Protection Zones to ensure that the risk of pollution to these valuable resources is not compromised. Details can be obtained from the government website:

<https://www.gov.uk/guidance/groundwater-source-protection-zones-spzs#find-groundwater-spzs>

If your site is in a Groundwater Source Protection Zone, you should have regard to the Environment Agency's approach to Groundwater Protection. Information on this is available via the link below:

<https://www.gov.uk/government/publications/groundwater-protection-position-statements>

Please note that such a location could have implications for the principle of your development and the need for additional mitigating measures to protect the groundwater environment and public water supply in the detailed design of your site.

Highway Drainage

If an evidence based assessment has been carried out and confirms that infiltration is not feasible, we recommend that you investigate the possibility of draining surface water to the highway drain where this ultimately discharges to a watercourse, by contacting the relevant Highway Authority.

Public Sewer

In accordance with the hierarchy of drainage options within the National Planning Practice Guidance, both discharge to ground via infiltration and discharge to a waterbody should be discounted prior to consideration of discharging surface water to the public sewer system. Evidence should be provided to demonstrate how these have been discounted, as outlined in the North West SuDS pro-forma.

Once evidence is provided as outlined above, United Utilities will consider a connection to the public surface water sewer within Oxbrow Way located South of the proposed site at a pass forward flow to be agreed by the Lead Local Flood Authority. United Utilities request that any agreed rate does not exceed 6.4l/s.

The Sewer records in this area are incomplete and we are unable to confirm pipe diameters. We would recommend Investigation as part of enabling works to verify this.

As a Water Company, we have no obligation to accept highway drainage into our public sewer network. However, should your proposals include runoff from highways, we would request that consideration is given to SuDS components that deliver source control are incorporated within the design of the scheme to reduce the volume and frequency of discharges of these flows to the public sewer.

Levels

For low-lying sites, (where the ground level of the site or the level of a basement is below the ground level at the point where the drainage connects to the public sewer), care should be taken to ensure that the property is not at increased risk of flooding. If these circumstances exist, we recommend that you contact us to discuss further. It could affect the detailed design of your site and result in the need to incorporate appropriate mitigating measures in your drainage scheme.

The area to the West of the site is topographically elevated above the proposed development. Sewers by design can surcharge but are only designed to hold a finite quantity of flow. In extreme events, sewers can experience flooding. Given that there are sewers located on elevated ground to your site and some located on-site, we would request that any potential exceedance routes are taken into consideration in order to protect the proposed dwellings.

We note there are multiple locations on-site where properties are set lower than the cover levels of existing manholes. As a result, should these ever flood, the adjacent properties could be at risk.

Land drainage / Overland flows / track drainage

United Utilities have no obligation, and furthermore we do not accept land drainage, overland flows or track drainage into the public sewerage network under any circumstances

Sewer Adoptions

You have indicated on your application form that you intend to put the sewers forward for adoption (including any SuDS components that can come within the meaning of a sewer).

United Utilities assess adoption applications based on the current Design & Construction Guidance and local practices which have now replaced 'Sewers For Adoption 6th Edition'.

We recommend that you submit a pre design assessment to the sewer adoption mailbox (SewerAdoptions@uuplc.co.uk) stating pre design assessment in the title

Please refer to links below to obtain further guidance:

<https://www.unitedutilities.com/builders-developers/larger-developments/wastewater/sewer-adoptions/>

Site drainage must be designed in accordance with Building Regulations, National Planning Policy, and local flood authority guidelines, we would recommend that you speak and make suitable agreements with the relevant statutory bodies.

If you intend to put forward your wastewater assets for adoption by United Utilities, the proposed detail design will be subject to a technical appraisal by an Adoption Engineer as we need to be sure that the proposals meet the requirements set out in the Design & Construction Guidance. The proposed design should give consideration to long term operability and give United Utilities a safe and cost effective proposal for the lifetime of the assets. In these cases, we strongly recommend that no construction commences until the detailed drainage design, submitted as part of the Section 104 application, has been assessed and accepted in writing by United Utilities. Any work carried out prior to the technical assessment being approved is done entirely at the developer's own risk and could be subject to change.

SuDS

If your development proposal incorporates any SuDS component(s) which interact with a sewer network you plan on offering for adoption to United Utilities; contact should be made with our technical team at your earliest convenience, please complete the 'Section 104 pre-application form : ' and include as much relevant detail as you can. These discussions can help prevent delays later in the development process.

Section 104 Pre application form (1b)

As per the sewerage sector guidance, all SuDS should be designed in accordance with the

standards within the Design & construction guidance & the CIRIA SuDS manual (C753)

Codes For Adoption

The new Codes for Adoption are outlined on the Water UK Website. The link below takes you to their webpage:

<https://www.water.org.uk/technical-guidance/developers-services/codes-for-adoption/>

A free copy of the new Design & Construction Guidance can be downloaded via the link below:

<https://www.water.org.uk/wp-content/uploads/2020/03/SSG-App-C-Des-Con-Guide-v-2-100320-C.pdf>

Existing Wastewater Assets Crossing the Site

According to our public sewer records there are public sewers located within your site boundary. We will require unrestricted access to the sewer for maintenance purposes, we would ask that you maintain a minimum clearance of 6m which is measured 3m from the centre line of the pipe unless there happens to be a formal easement agreement in place, in which case the specified easement width would apply.

We note, that there is an existing public combined sewer which has been suggested to be located in rear gardens, this reduces future access for maintenance purposes and does not represent best practice. As a result you may wish to reconsider the site layout or a sewer diversion.

Please refer to the link below to obtain full details of the processes involved with sewer diversions:

<https://www.unitedutilities.com/builders-developers/larger-developments/wastewater/sewer-diversions/>

-
-

Existing Water Assets Crossing the Site

It is the developer responsibility to identify utilities on-site. Where clean water assets are shown on our records, we recommend that you contact our Water Pre-Development Team, via the following email address: DeveloperServicesWater@uuplc.co.uk. Further information for this service can be found on our website via the link below:

<https://www.unitedutilities.com/builders-developers/larger-developments/pre-development/water-pre-dev/>

Connection Application

Although we may discuss and agree discharge points and rates in principle, please be aware that you will have to apply for a formal sewer connection. This is so that we can assess the method of construction, Health & Safety requirements and to ultimately inspect the connection when it is made. Details of the application process and the form itself can be obtained from our website by following the link below:

<https://www.unitedutilities.com/builders-developers/larger-developments/wastewater/sewer-connections/>

We recommend that the detailed design should confirm the locations of all utilities in the area and ensure that any proposed drainage solution considers routing and clash checks where required.

If we can be of any further assistance please don't hesitate to contact us further.

Kind regards,

Kind regards



Mike Duckworth

Developer Services Engineer
Developer Services & Metering
Customer Services

T: 07768702161
unitedutilities.com

If you have received a great service today why not tell us?

Visit: [unitedutilities.com/wow](https://www.unitedutilities.com/wow)

The information contained in this e-mail is intended only for the individual to whom it is addressed. It may contain legally privileged or confidential information or otherwise be exempt from disclosure. If you have received this Message in error or there are any problems, please notify the sender immediately and delete the message from your computer. You must not use, disclose, copy or alter this message for any unauthorised purpose. Neither United Utilities Group PLC nor any of its subsidiaries will be liable for any direct, special, indirect or consequential damages as a result of any virus being

passed on, or arising from the alteration of the contents of this message by a third party.

United Utilities Group PLC, Haweswater House, Lingley Mere
Business Park, Lingley Green Avenue, Great Sankey,
Warrington, WA5 3LP
Registered in England and Wales. Registered No 6559020

www.unitedutilities.com
www.unitedutilities.com/subsidiaries