HATCHING KEY

Provide & lay 40mm thick bitumen macadam to BS4987 base course with 20mm nominal size limestone aggregate & 20mm thick bitumen macadam to BS4987 wearing course with 6mm nominal size basalt or granite aggregate. Refer to NBS Q10, Q20, Q22

89.00 indicates new levels

Excavate to remove existing surface, Supply & lay new turf to BS3969, cut size 900x300x25mm thick, The Contractor shall roll and chain harrow or rake the site to produce a suitable turf bed preparation. Any surplus vegetable matter, rubbish, etc to be removed by the Contractor, Pre-turf fertiliser shall be applied seven days before turfing, The finished levels of turf abutting paving, mowing margins or tops of kerbs must not be less than 25mm. Topsoil shall be spread to a min. depth of 75mm in areas to be turfed. Refer to NBS Q10, Q28, Q30

Supply & plant shrubbery /bushes
Topsoil shall be spread

Supply & plant new trees etc...
Bat Survey recommendation:- tree planting as part of this project should be native species. Rowan, Holly, Hawthorn, Guelder Rose and Bird Cherry are recommended as they are small trees with attractive blossom and fruit.

Existing trees retained.

REV	DESCRIPTION	DATE

planning issue

This design/document has been prepared by Bury MBC Architectural Services. It should not, without prior permission, be used for any use other than the use originally intended.

Department Of Operations
Architectural Services
3 Knowsley Place,
Duke Street,
Bury, Lancs BL9 0EJ
Bury | Prestwich | Radcliffe | Ramsbottom | Tottington | Whitefield

PROJECT TITLE:
Park View Primary School
Park View Road, Prestwich. M25 1FA
Replacement Classrooms

DRAWING TITLE:
Proposed External Works Plan

DRAWN BY: RV-M	DATE: 10/20	ISSUE NUMBER:	
CHECKED BY: NB	DATE: 10/20	DATE OF ISSUE:	
SCALE: 1:100 @ A1			

DRAWING NUMBER:
E 19317 A E02
DEPT | CODE | DRAWING REF. | REV