

Site:- St Hilda's School, Prestwich.

Section A.

Take down and remove from site 1 No. single leaf gate.

Supply and erect 7.2 Mtrs of 800mm. high 656 mesh fencing fixed with brackets to cranked posts, allowing 450mm. down back of wall with 2 No. bolt fixings and 215mm. across top of wall with 1 No. fixing into top (450mm. down back of wall to prevent accidents with children) RAL 5010

Supply & erect 1 No single leaf gate: 1200mm wide x 2400mm high, clad with 656 mesh, slide latch, drop bolt, gate posts fixed to brickwork. RAL 5010

Section B.

Take down and remove 21 Mtrs of fencing and single leaf gate

Supply and erect 21 Mtrs of 2.4 Mtr high 656 fencing system with posts set into ground, galvanised and coated RAL 5010.

Supply & erect 1 No single leaf gate: 1200mm wide x 2400mm high, clad with 656 mesh, slide latch, drop bolt, gate posts set in concrete. RAL 5010

Section C.

Take down and remove 21 Mtrs of fencing and 2 No. single leaf gates.

Supply and erect 21 Mtrs of 2.4 Mtr high 656 fencing system RAL 5010 as above.

Supply & erect 1 No single leaf gate: 1200mm wide x 2400mm high, clad with 656 mesh, slide latch, drop bolt, gate posts set in concrete. RAL 5010

Supply & erect 1 No single leaf gate: 1500mm wide x 2400mm high, clad with 656 mesh, slide latch, drop bolt, gate posts set in concrete or fixed to brickwork. RAL 5010

Section D.

Take down and remove from site 20 Mtrs of fencing, 1 No. single leaf gate and 1 Pair of double leaf gates.

Supply and erect 20 Mtrs of 2.4 Mtr high 656 fencing RAL 5010.

Supply & erect 1 No single leaf gate: 1200mm wide x 2400mm high, clad with 656 mesh, slide latch, drop bolt, gate posts set in concrete. RAL 5010

Supply & erect 1 No double leaf gate: 3000mm wide x 2400mm high, clad with 656 mesh, slide latch, drop bolt, gate posts set in concrete or fixed to brickwork. RAL 5010

Additional temporary fencing.

2 Mtr of 800mm. on wall

10 Mtrs of mesh panels fixed to existing fencing

3 Mtrs of 1.8 Mtr high fencing