



- Structural Engineering
- Civil Engineering
- Hydrology

**Let's Develop  
Your Tomorrow  
Today**

**The Waterside Village – Opulwood  
FRA Addendum  
Date: 31.10.2024**



+44 (0)1925 243333



[UK@ELLUCProjects.com](mailto:UK@ELLUCProjects.com)



760 Mandarin Court, Centre Park,  
Warrington, Cheshire WA1 1GG

### Document History and Status

| Revision | Date     | Purpose/Statu | Author | File Ref | Check | Review |
|----------|----------|---------------|--------|----------|-------|--------|
| 1        | 25.04.23 | Information   | IC     | 22006    | SF    | SF     |
| 2        | 19.07.23 | Information   | IC     | 22006    | SF    | SF     |
| 3        | 31.10.24 | Information   | DW     | 22006    | DW    | DW     |

This document has been prepared in accordance with the scope of Elluc Projects appointment with its client and is subject to the terms of the appointment. It is addressed to and for the sole use and reliance of Elluc Project's client. Elluc Projects accepts no liability for any use of this document other than by its client and only for the purposes, stated in the document, for which it was prepared and provided. No person other than the client may copy (in whole or in part) use or rely on the contents of this document, without the prior written permission of the Elluc Projects Limited. Any advice, opinions, or recommendations within this document should be read and relied upon only in the context of the document as a whole. The contents of this document are not to be construed as providing legal, business or tax advice or opinion.

© Elluc Projects Limited 2023

### Document Details

|                       |                                                                                                                         |
|-----------------------|-------------------------------------------------------------------------------------------------------------------------|
| <b>Last saved</b>     | 31.10.2024                                                                                                              |
| <b>Path</b>           | ELLUC Projects Group - Drive\Projects\2200_References\22006 - The Waterside Village - Opulwood Developments\F - Reports |
| <b>Author</b>         | D WOOD                                                                                                                  |
| <b>Project Number</b> | 22006                                                                                                                   |
| <b>Project Name</b>   | The Waterside Village - Opulwood Developments                                                                           |

## **1.0 Introduction**

Elluc Projects have been commissioned by Opulwood Developments to provide an addendum to the existing Flood Risk Assessment by BEK Enviro Ltd. report Ref: BEK-18439-1-Rev A dated December 2018.

Specifically, the planners for this development site have requested the drainage engineers to check if any updated flood data was used in the design calculations for the drainage design carried out by Elluc.

## **2.0 Proposed drainage design**

The proposed drainage design shown in drawing ELL-22006-OP-L-120 within Appendix A shows a new private surface water and foul drainage system serving the development and combining to a combined drain just before connecting to the public combined sewer in Kay Street.

A hydrobrake flow control is proposed to limit surface water discharge to 5 l/s to 1 in 100 year plus climate change allowance.


The proposed drainage design follows the hierarchy of surface water outfalls, due to the nature of the site and the practicalities of constructing a headwall outfall to the River Irwell a connection to the combined sewer is proposed. A public surface water sewer isn't available near to the site to connect to.

The public combined sewer is approximately 3.5m lower than the proposed surface and foul connections which backdrop into the combined demarcation manhole before leaving site. The risk of backing up of the sewers because of this and no direct connection to the river is considered low. The drainage calculations are provided in Appendix B.


## **3.0 Summary**

The proposed drainage design shown in Appendix A and the calculations in Appendix B demonstrate the site can be drained safely, with regard to flood risk described in the BEK Enviro report. A majority of the flood risk is mitigated by the use of elevated external works and FFL's to the development set in line with the FRA report.

## APPENDIX A



- NOTES
1. ALL ADAPTABLE DRAINAGE WORKS HAVE BEEN DESIGNED AND ARE TO BE CONSTRUCTED IN ACCORDANCE WITH "DESIGN AND CONSTRUCTION GUIDANCE FOR FOUL AND SEWER ADOPTION - SEWER SECTOR GUIDANCE" AND WATER AUTHORITY SUPPLEMENT GUIDELINES AND STANDARD DETAILS.
  2. ALL CLAY PIPE WORK SHALL BE EXTRA STRENGTH CLAYWARE TO B.S EN 295:1991 PART 1
  3. ALL PRECAST CONCRETE PIPEWORK SHALL BE TO THE CLASS STATED ON THE DRAWINGS IN ACCORDANCE WITH B.S EN 1916:2002. ALSO, ALL MANHOLES AND CHAMBERS SHALL BE TO B.S EN 1917:2002
  4. THE CONTRACTOR MAY ELECT TO USE REINFORCED PVC PIPES AS COVERED BY B.S 4660:2000 & B.S EN 1401-1. STRUCTURED WALL U/PVC PIPES TO COMPLY WITH WIS 4-35-01 UPTO AND INCLUDING 300MM. (BY PRIOR AGREEMENT WITH ADOPTING AUTHORITY) MAX. PIPE LENGTH TO BE 3.0M
  5. ALL LEVELS RELATE TO TOPOGRAPHICAL SURVEY DATUM
  6. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS
  7. PLOT DRAINAGE CONNECTIONS TO SEWERS MUST BE 150mm DIAMETER AND UNLESS OTHERWISE STATED LAID TO THE INVERT SHOWN.
  8. LEVELS GIVEN ON DRAGOUT CHAMBERS ARE INCOMING PIPE LEVELS
  9. PLOT DRAINAGE RUNS TO BE KEPT WITHIN THE CURTILAGE OF THE PLOT THEY SERVE WHEREVER POSSIBLE.
  10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT ANY EXISTING INVERT LEVELS AND EXISTING SITE LEVELS (EXISTING BOUNDARY LEVELS) INDICATED ON DRAWINGS ARE CORRECT BEFORE WORKS COMMENCE.
  11. ALL CONNECTIONS TO ADAPTABLE SEWERS SHALL BE MANUFACTURED JUNCTION PIPES. SADDLE CONNECTIONS WILL NOT BE PERMITTED, UNLESS SPECIFIED.
  12. ALL SEWERS FOR ADOPTION WITH GREATER THAN 1.20M COVER IN ROADS OR 0.9m COVER IN FIELDS SHALL HAVE CLASS S GRANULAR BED AND SURROUND.
  13. ANY SEWER FOR ADOPTION WITH LESS THAN 1.2M COVER IN ROADS OR 0.9m COVER IN FIELDS SHALL HAVE A MINIMUM OF 150mm ST4 CONCRETE SURROUND. FLEXIBILITY SHALL BE MAINTAINED BY THE PROVISION OF FLEXCELL OR SIMILAR APPROVED JOINT FILLER BREAKS IN THE CONCRETE SURROUND AT EACH PIPE JOINT
  14. IT IS THE RESPONSIBILITY FOR THE CONTRACTOR TO CHECK ALL ONSITE EXISTING GROUND LEVELS PRIOR TO COMMENCING AND IF THERE ARE ANY DISCREPANCIES THE CONTRACTOR MUST REPORT TO THE ENGINEER IMMEDIATELY
  15. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE DRAINAGE AUTHORITY OF THE COMMENCEMENT OF ANY DRAINAGE WORKS AND TO COMPLETE ANY REQUIRED SEWER CONNECTION FORMS INCLUSIVE OF PAYING ANY REQUIRED FEES. THE CONTRACTOR MUST ALLOW FOR THE SUPERVISION OF THE SEWER CONSTRUCTION WORKS BY THE LOCAL AUTHORITY AND NOTIFY THE SUPERVISING OFFICER, GIVING NOTICE WHICH IN ACCORDANCE WORTH THE LA REQUIREMENTS.
  16. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO APPLY FOR ANY REQUIRED ROAD OPENING PERMITS WITH THE LOCAL AUTHORITY INCLUDING THE PAYMENT OF ANY FEES
  17. BEFORE COMMENCING ANY WORKS ON SITE, THE CONTRACTOR MUST CONTACT THE RELEVANT STATUTORY UNDERTAKER AND BE IN POSSESSION OF THE LATEST AVAILABLE DRAWINGS FROM THE STATUTORY UNDERTAKERS WHICH SHOWS DETAILS OF THEIR SERVICES/APPARATUS. THE CONTRACTOR MUST CONFIRM EXACT LOCATION AND DEPTH OF ANY SERVICES/APPARATUS BY THE USE OF ELECTROLOCATION OR SIMILAR DEVICES AND BY HAND DUG TRIAL HOLES. MECHANICAL EXCAVATOR, POWER TOOLS ETC. MUST NOT BE USED TO LOCATE EXISTING SERVICES/APPARATUS.
  18. COUNCILS HIGHWAY SUPERVISION OFFICER REQUIRED ONSITE THROUGHOUT CONSTRUCTION. DESIGN SUBJECT TO CBR TESTING TO BE AGREED WITH HIGHWAYS OFFICER ONSITE.
  19. SUBJECT TO HIGHWAYS APPROVAL
  20. SUBJECT TO WATER AUTHORITY APPROVAL.
  21. ALL PIPES TO BE 100mm DIAMETER UNLESS OTHERWISE STATED. ALL SURFACE WATER LATERAL CONNECTIONS TO BE 150mm DIAMETER.



**KEY:**

- PROPOSED SURFACE WATER RUN
- PROPOSED SURFACE WATER CHAMBER
- PROPOSED SURFACE WATER RODDING EYE
- PROPOSED FOUL WATER RUN
- PROPOSED FOUL WATER CHAMBER
- PROPOSED SURFACE WATER MANHOLE AND SEWER
- PROPOSED SURFACE WATER ATTENUATION TANK
- FINISHED FLOOR LEVEL
- PROPOSED PRIVATE ROAD GULLY (RODDABLE AND DRAINAGE POINT SITE BOUNDARY)

|   |                                                  |          |    |    |
|---|--------------------------------------------------|----------|----|----|
| D | UPDATED TO SUIT NEW ARCHITECT LAYOUT / SCHEME.   | 31.10.24 | DW | JC |
| C | UPDATED FLOW CONTROL DETAILS.                    | 14.11.23 | IC | IC |
| B | UPDATED TO SUIT NEW ARCHITECT LAYOUT / SCHEME.   | 02.06.23 | IC | IC |
| A | UPDATED TO SUIT SEWER RECORDS / DRAINAGE SURVEY. | 25.04.23 | IC | IC |

Rev: Description: Date: By: Chkd:

Status: PRELIMINARY

Client: MAPLE CONSTRUCTION (NW) LTD

Project: THE WATERSIDE VILLAGE

Dwg Title: PRIVATE DRAINAGE LAYOUT

**ELLUC Projects**

ELLUC PROJECTS  
423 KIRKSTALL ROAD  
AIREDALE HOUSE  
LEEDS  
LS4 2EW

t: (0113) 357 2100  
info@ellucprojects.co.uk  
www.ellucprojects.co.uk

|        |       |              |        |          |      |
|--------|-------|--------------|--------|----------|------|
| Scale: | Size: | First Issue: | Drawn: | Checked: | Rev: |
| 1:100  | A1    | 07.03.22     | IC     | MJS      | D    |

Drawing No: ELL-22006-OP-L-120

## APPENDIX B

|                                              |                                      |                                                                                     |
|----------------------------------------------|--------------------------------------|-------------------------------------------------------------------------------------|
| ELLUC Projects Ltd                           |                                      | Page 1                                                                              |
| 760 Mandarin Court<br>Warrington<br>Cheshire | 22006 - Waterside<br>SW Calculations |  |
| Date 01/07/2023                              | Designed by IC                       |                                                                                     |
| File 22006 - SW network calcu...             | Checked by                           |                                                                                     |
| XP Solutions                                 | Network 2017.1.1                     |                                                                                     |

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

| PN    | Length<br>(m) | Fall<br>(m) | Slope<br>(1:X) | I.Area<br>(ha) | T.E.<br>(mins) | Base<br>Flow (l/s) | k<br>(mm) | HYD<br>SECT | DIA<br>(mm) | Section Type | Auto<br>Design                                                                      |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|--------------|-------------------------------------------------------------------------------------|
| 1.000 | 14.278        | 0.096       | 148.7          | 0.037          | 5.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |  |
| 1.001 | 1.121         | 0.171       | 6.6            | 0.098          | 0.00           | 0.0                | 0.600     | o           | 225         | Pipe/Conduit |  |
| 1.002 | 14.000        | 0.063       | 222.2          | 0.000          | 0.00           | 0.0                | 0.600     | []          | -1          | Pipe/Conduit |  |
| 1.003 | 5.043         | 0.022       | 229.2          | 0.000          | 0.00           | 0.0                | 0.600     | o           | 225         | Pipe/Conduit |  |
| 1.004 | 5.943         | 0.421       | 14.1           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |  |
| 1.005 | 8.138         | 0.814       | 10.0           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |  |

Network Results Table

| PN    | Rain<br>(mm/hr) | T.C.<br>(mins) | US/IL<br>(m) | E I.Area<br>(ha) | E Base<br>Flow (l/s) | Foul<br>(l/s) | Add Flow<br>(l/s) | Vel<br>(m/s) | Cap<br>(l/s) | Flow<br>(l/s) |
|-------|-----------------|----------------|--------------|------------------|----------------------|---------------|-------------------|--------------|--------------|---------------|
| 1.000 | 50.00           | 5.29           | 106.986      | 0.037            | 0.0                  | 0.0           | 0.0               | 0.82         | 14.5         | 5.0           |
| 1.001 | 50.00           | 5.29           | 106.815      | 0.135            | 0.0                  | 0.0           | 0.0               | 5.14         | 204.5        | 18.3          |
| 1.002 | 50.00           | 5.38           | 106.810      | 0.135            | 0.0                  | 0.0           | 0.0               | 2.72         | 10326.3      | 18.3          |
| 1.003 | 50.00           | 5.48           | 106.747      | 0.135            | 0.0                  | 0.0           | 0.0               | 0.86         | 34.2         | 18.3          |
| 1.004 | 50.00           | 5.51           | 106.725      | 0.135            | 0.0                  | 0.0           | 0.0               | 2.70         | 47.6         | 18.3          |
| 1.005 | 50.00           | 5.56           | 104.804      | 0.135            | 0.0                  | 0.0           | 0.0               | 3.21         | 56.6         | 18.3          |

Conduit Sections for Storm

NOTE: Diameters less than 66 refer to section numbers of hydraulic conduits. These conduits are marked by the symbols:- [] box culvert, \/ open channel, oo dual pipe, ooo triple pipe, O egg.

Section numbers < 0 are taken from user conduit table

| Section<br>Number | Conduit<br>Type | Major<br>Dimn.<br>(mm) | Minor<br>Dimn.<br>(mm) | Side<br>Slope<br>(Deg) | Corner<br>Splay<br>(mm) | 4*Hyd<br>Radius<br>(m) | XSect<br>Area<br>(m <sup>2</sup> ) |
|-------------------|-----------------|------------------------|------------------------|------------------------|-------------------------|------------------------|------------------------------------|
| -1                | []              | 4750                   | 800                    | 90.0                   |                         | 1.369                  | 3.800                              |



|                                                     |  |                                      |
|-----------------------------------------------------|--|--------------------------------------|
| ELLUC Projects Ltd                                  |  | Page 3                               |
| 760 Mandarin Court<br>Warrington<br>Cheshire        |  | 22006 - Waterside<br>SW Calculations |
| Date 01/07/2023<br>File 22006 - SW network calcu... |  | Designed by IC<br>Checked by         |
| XP Solutions                                        |  | Network 2017.1.1                     |



PIPELINE SCHEDULES for Storm

Upstream Manhole

| PN    | Hyd Sect | Diam (mm) | MH Name      | C.Level (m) | I.Level (m) | D.Depth (m) | MH Connection | MH DIAM., L*W (mm) |
|-------|----------|-----------|--------------|-------------|-------------|-------------|---------------|--------------------|
| 1.000 | o        | 150       | S1           | 108.550     | 106.986     | 1.414       | Open Manhole  | 450                |
| 1.001 | o        | 225       | S2 (CP)      | 108.860     | 106.815     | 1.820       | Open Manhole  | 1350               |
| 1.002 | [ ]      | -1        | TANK IN      | 108.600     | 106.810     | 0.990       | Open Manhole  | 450                |
| 1.003 | o        | 225       | TANK OUT     | 108.600     | 106.747     | 1.628       | Open Manhole  | 450                |
| 1.004 | o        | 150       | FLOW CONTROL | 108.602     | 106.725     | 1.727       | Open Manhole  | 2100               |
| 1.005 | o        | 150       | CW1          | 108.700     | 104.804     | 3.746       | Open Manhole  | 1350               |

Downstream Manhole

| PN    | Length (m) | Slope (1:X) | MH Name      | C.Level (m) | I.Level (m) | D.Depth (m) | MH Connection | MH DIAM., L*W (mm) |
|-------|------------|-------------|--------------|-------------|-------------|-------------|---------------|--------------------|
| 1.000 | 14.278     | 148.7       | S2 (CP)      | 108.860     | 106.890     | 1.820       | Open Manhole  | 1350               |
| 1.001 | 1.121      | 6.6         | TANK IN      | 108.600     | 106.644     | 1.731       | Open Manhole  | 450                |
| 1.002 | 14.000     | 222.2       | TANK OUT     | 108.600     | 106.747     | 1.053       | Open Manhole  | 450                |
| 1.003 | 5.043      | 229.2       | FLOW CONTROL | 108.602     | 106.725     | 1.652       | Open Manhole  | 2100               |
| 1.004 | 5.943      | 14.1        | CW1          | 108.700     | 106.304     | 2.246       | Open Manhole  | 1350               |
| 1.005 | 8.138      | 10.0        |              | 108.750     | 103.990     | 4.610       | Open Manhole  | 1500               |

Free Flowing Outfall Details for Storm

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (m) | D, L (mm) | W (mm) |
|---------------------|--------------|--------------|--------------|------------------|-----------|--------|
| 1.005               |              | 108.750      | 103.990      | 0.000            | 1500      | 0      |

Simulation Criteria for Storm

|                                 |       |                                     |       |
|---------------------------------|-------|-------------------------------------|-------|
| Volumetric Runoff Coeff         | 0.750 | Additional Flow - % of Total Flow   | 0.000 |
| Areal Reduction Factor          | 1.000 | MADD Factor * 10m³/ha Storage       | 2.000 |
| Hot Start (mins)                | 0     | Inlet Coefficient                   | 0.800 |
| Hot Start Level (mm)            | 0     | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins)                     | 60    |
| Foul Sewage per hectare (l/s)   | 0.000 | Output Interval (mins)              | 1     |


Number of Input Hydrographs 0    Number of Offline Controls 0    Number of Time/Area Diagrams 0  
Number of Online Controls 1    Number of Storage Structures 0    Number of Real Time Controls 0

Synthetic Rainfall Details

©1982-2017 XP Solutions





|                                                     |  |                                                                                     |
|-----------------------------------------------------|--|-------------------------------------------------------------------------------------|
| ELLUC Projects Ltd                                  |  | Page 6                                                                              |
| 760 Mandarin Court<br>Warrington<br>Cheshire        |  |  |
| 22006 - Waterside<br>SW Calculations                |  |                                                                                     |
| Date 01/07/2023<br>File 22006 - SW network calcu... |  |                                                                                     |
| Designed by IC<br>Checked by                        |  |                                                                                     |
| XP Solutions                                        |  | Network 2017.1.1                                                                    |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

|                                 |       |                                     |       |
|---------------------------------|-------|-------------------------------------|-------|
| Areal Reduction Factor          | 1.000 | Additional Flow - % of Total Flow   | 0.000 |
| Hot Start (mins)                | 0     | MADD Factor * 10m³/ha Storage       | 2.000 |
| Hot Start Level (mm)            | 0     | Inlet Coeffiecient                  | 0.800 |
| Manhole Headloss Coeff (Global) | 0.500 | Flow per Person per Day (l/per/day) | 0.000 |
| Foul Sewage per hectare (l/s)   | 0.000 |                                     |       |

Number of Input Hydrographs 0    Number of Offline Controls 0    Number of Time/Area Diagrams 0  
Number of Online Controls 1    Number of Storage Structures 0    Number of Real Time Controls 0

Synthetic Rainfall Details

|                          |             |             |       |
|--------------------------|-------------|-------------|-------|
| Rainfall Model           | FSR         | Ratio R     | 0.254 |
| Region England and Wales | Cv (Summer) |             | 0.750 |
| M5-60 (mm)               | 19.000      | Cv (Winter) | 0.840 |

Margin for Flood Risk Warning (mm) 450.0  
Analysis Timestep 2.5 Second Increment (Extended)  
DTS Status ON  
DVD Status ON  
Inertia Status OFF

Profile(s) Summer and Winter  
Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440  
Return Period(s) (years) 100  
Climate Change (%) 45

| PN    | US/MH Name   | Storm      | Return Period | Climate Change | First (X) Surge | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|--------------|------------|---------------|----------------|-----------------|-----------------|--------------------|---------------|
| 1.000 | S1           | 120 Winter | 100           | +45%           | 100/15 Summer   |                 |                    |               |
| 1.001 | S2 (CP)      | 120 Winter | 100           | +45%           | 100/15 Summer   |                 |                    |               |
| 1.002 | TANK IN      | 120 Winter | 100           | +45%           | 100/120 Winter  |                 |                    |               |
| 1.003 | TANK OUT     | 120 Winter | 100           | +45%           | 100/15 Summer   |                 |                    |               |
| 1.004 | FLOW CONTROL | 120 Winter | 100           | +45%           | 100/15 Summer   |                 |                    |               |
| 1.005 | CW1          | 360 Summer | 100           | +45%           |                 |                 |                    |               |

| PN    | US/MH Name | Water Level (m) | Surcharged Depth (m) | Flooded Volume (m³) | Flow / Cap. | Overflow (l/s) | Pipe Flow (l/s) | Status     | Level Exceeded |
|-------|------------|-----------------|----------------------|---------------------|-------------|----------------|-----------------|------------|----------------|
| 1.000 | S1         | 107.622         | 0.486                | 0.000               | 0.57        |                | 7.6             | SURCHARGED |                |
| 1.001 | S2 (CP)    | 107.617         | 0.577                | 0.000               | 0.47        |                | 27.6            | SURCHARGED |                |
| 1.002 | TANK IN    | 107.616         | 0.006                | 0.000               | 0.01        |                | 27.5            | SURCHARGED |                |

©1982-2017 XP Solutions

|                                              |                                      |                                                                                     |
|----------------------------------------------|--------------------------------------|-------------------------------------------------------------------------------------|
| ELLUC Projects Ltd                           |                                      | Page 7                                                                              |
| 760 Mandarin Court<br>Warrington<br>Cheshire | 22006 - Waterside<br>SW Calculations |  |
| Date 01/07/2023                              | Designed by IC                       |                                                                                     |
| File 22006 - SW network calcu...             | Checked by                           |                                                                                     |
| XP Solutions                                 | Network 2017.1.1                     |                                                                                     |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1)  
for Storm

| PN    | US/MH<br>Name | Water        | Surcharged   | Flooded        | Pipe           |                   | Status | Level<br>Exceeded |
|-------|---------------|--------------|--------------|----------------|----------------|-------------------|--------|-------------------|
|       |               | Level<br>(m) | Depth<br>(m) | Volume<br>(m³) | Flow /<br>Cap. | Overflow<br>(l/s) |        |                   |
| 1.003 | TANK OUT      | 107.616      | 0.644        | 0.000          | 0.23           |                   | 5.7    | SURCHARGED        |
| 1.004 | FLOW CONTROL  | 107.632      | 0.757        | 0.000          | 0.12           |                   | 4.9    | SURCHARGED        |
| 1.005 | CW1           | 104.835      | -0.119       | 0.000          | 0.10           |                   | 4.9    | OK                |