



STAR RADCLIFFE ACADEMY

OUTLINE DRAINAGE STRATEGY

Project No:2303-02
August 2023
FS1013-REN-XX-XX-T-C-0161
Rev: P02

This report has been prepared for the sole benefit, use and information of **The Department for Education** for the purposes set out in the report or instructions commissioning it. The liability of **renaissance** in respect of the information contained in the report will not extend to any third party. This document should not be used in whole or part by any third parties without the express written permission of **renaissance**. If any unauthorised third party comes into possession of this report, they rely on it at their own risk and **renaissance** do not owe them any Duty of Care.

author	Henry Wilkinson MEng
date	11.08.2023
approved	Philip Whitesmith MEng, CEng, MStructE
date	11.08.2023

Contact Details:

Carvers Warehouse, 77 Dale Street

Manchester, M1 2HG

t: 0161 393 650

Revision	Description	Issued by	Date	Checked
P02	Checking comments incorporated	H Wilkinson	08.09.2023	P Whitesmith
P01	Preliminary issue	H Wilkinson	11.08.2023	P Whitesmith

CONTENTS

1.0	INTRODUCTION	1
1.1	Purpose of this report	1
2.0	THE SITE	2
2.1	Site Location	2
2.1	Site Description	2
2.2	Existing Site Drainage	2
2.3	Geology	3
2.4	Hydrology and Hydrogeology	3
2.5	Proposed Development	4
3.0	EXISTING & PROPOSED SURFACE WATER DISCHARGE RATES	5
3.1	Pre-Development Surface Water Run-Off Rates	5
3.2	Proposed Surface Water Discharge Rates	6
3.3	Attenuation Requirements	6
4.0	SURFACE WATER DISCHARGE & SUDS ASSESSMENT	7
4.1	Surface Water Discharge Assessment	7
4.2	Sustainable Urban Drainage	7
4.3	Water Quality Assessment	8
5.0	OUTLINE DRAINAGE STRATEGY	10
5.1	Surface Water System	10
5.2	Foul Water System	10
5.3	Phasing & Surface Water Management During Construction	11
6.0	FUTURE MANAGEMENT & MAINTENANCE	12
6.1	General Maintenance & Inspection Requirements	12
6.2	Inspection Chambers, Manholes and Catchpits	13
6.3	Pipes	13
6.4	Drainage Channels and Gullies	13
6.5	Flow Control Device	14
6.6	Permeable Pavements	14
6.7	Extended Detention Basin	15
6.8	Tree Pits	16

APPENDICES

APPENDIX A	Existing Topographical and Utilities Survey Information
APPENDIX B	United Utilities Sewer Records
APPENDIX C	Proposed Development Plans
APPENDIX D	Existing Impermeable Areas Plan
APPENDIX E	InfoDrainage Greenfield Run-off Rates
APPENDIX F	Proposed Impermeable Areas Plan
APPENDIX G	InfoDrainage Quick Storage Estimate
APPENDIX H	Below Ground Drainage General Arrangement
APPENDIX I	Proposed Surface Water Micro Drainage Calculations

1.0 INTRODUCTION

1.1 Purpose of this report

This Outline Drainage Strategy has been prepared to support the planning application for the proposed Star Radcliffe Academy development.

The assessment includes a summary of the site, an estimate of the existing and proposed surface water discharge rates, an infiltration assessment, a SuDS assessment, and outline drainage proposals and performance criteria.

This report should be read in conjunction with the Flood Risk Assessment (renaissance, FS1013-REN-XX-XX-T-C-0160, August 2023).

The proposals within this report are intended to demonstrate the feasibility of the overarching drainage strategy to support the planning proposal.

2.0 THE SITE

2.1 Site Location

The proposed development site is located off Spring Lane, Radcliffe.

The site location is described below:

- Post Code M26 2SZ
- OS X (Easting) 378714
- OS Y (Northing) 407606
- Nat. Grid SD 787076

The site location is illustrated in Figure 2.1 below.



Imagery ©2022 Bluesky, Getmapping plc, Infoterra Ltd & Bluesky, Maxar Technologies, Map Data ©2022

Figure 2.1: Indicative Site Location

2.1 Site Description

The site is circa 4.56 hectares comprising approximately 43% impermeable hard standing. Based on aerial imagery and the topographical survey information (Appendix A), the site is occupied by a school (Spring Lane School) and leisure centre with swimming pool (Radcliffe Leisure Centre) in the south as well as tarmac hardstanding associated with car parking beyond. The north-west of the site is occupied by open grassland.

The topographical survey (Appendix A) indicates that the site lies approximately between 77.000m AOD at the north-western boundary and 69.300m AOD at the south-eastern boundary.

A 2300mm diameter surface water culvert is indicated to cross the southern portion of the site, flowing from west to east.

2.2 Existing Site Drainage

CCTV and utility surveys have been carried out to trace the existing drainage on site.

The foul drainage network associated with the existing buildings is indicated to discharge from the site on the eastern boundary underneath the Metrolink track, however, the survey information does not extend far enough to trace the connection into the public sewer network.

CCTV survey information indicates the surface water from the site discharges into the existing combined drainage and the culvert running beneath the southern portion of the site.

A further CCTV survey has been commissioned to confirm the connectivity of the culvert and existing combined drainage into the downstream sewer network / watercourse.

Refer to Appendix B for the United Utilities sewer records.

2.3 Geology

The lower south-eastern part of the site is largely underlain by granular made ground to about 2m depth overlying glacial till. Further granular made ground exists over the upper north-western part of the site but this is largely restricted to an area of former allotments. The natural ground in this area consists of glacial sand and gravel extending 4m in depth resting on glacial till.

The deeper solid geology is the Pennine Middle Coal Measures formation comprising mudstone, siltstone and sandstone. Boreholes have indicated that the depth to the bedrock varies from 12.6m to 20.5m below the existing ground level.

For further details, reference should be made to the phase 2 geo-environmental report produced by Geotechnics.

2.4 Hydrology and Hydrogeology

The closest surface water feature is the Manchester, Bolton and Bury Canal which lies 4m to the north of the site.

Based on the geology across the site, a summary of the Environment Agency aquifer designations is presented below:

STRATUM	COVERAGE	Aquifer Designation
Till, Devensian	Eastern portion of the site	Secondary Aquifer (Undifferentiated). The classification is assigned where it is not possible to attribute either category A or B to the aquifer
Glaciofluvial Sheet Deposits	Western portion of the site	Secondary A Aquifer. This geology is of high intergranular and/or fracture permeability, usually providing a high level of water storage and may support water supply/river base flow on a strategic level
Pennine Middle Coal Measures Formation	Full Site	Secondary A Aquifer. This geology is of high intergranular and/or fracture permeability, usually providing a high level of water storage and may support water supply/river base flow on a strategic level

Table 2.1 – EA Aquifer Designations of Site Geology

A summary of the pertinent hydrogeological features identified within the geo-environmental data report are provided below:

STRATUM	Distance (m) & Direction	Aquifer Designation
Nearest Groundwater Abstraction	250m	There are two entries within 250m relating to the same location, a pond/reservoir located 13m to the north-east (immediately north of the former Radcliffe West Fork Embankment). Water has been abstracted from a reservoir fed by surface water drainage for use as process water in the paper and printing industry

		initially by the East Lancashire Paper Mill Co. and then by St. Regis Paper Company U.K. Ltd.
--	--	---

Table 2.2 –Summary of Hydrogeological Features

2.5 Proposed Development

The proposed redevelopment consists of the demolition of the existing Spring Lane School and Radcliffe Leisure Centre (also known as Coney Green Leisure Centre). Following these demolition works it is proposed to construct a new 3-storey secondary school building along with a new artificial grass pitch, a multi-use games area (MUGA), a grass pitch, new car parking areas and access roads.

The proposed access road to the south of the site is to be adopted by Bury Council and so does not form part of our assessment of the onsite drainage as it will be covered under a separate design.

Refer to proposed development plans in Appendix C for further details of the proposed development.

3.0 EXISTING & PROPOSED SURFACE WATER DISCHARGE RATES

3.1 Pre-Development Surface Water Run-Off Rates

The privately drained area of the development site is approximately 4.56 Ha (45600m²) comprising 1.98 Ha (19800 m²) of impermeable area and 2.58 Ha (25800m²) of permeable soft landscaping. Refer to the topographical survey in Appendix A and existing drained areas plan in Appendix D for further details.

3.2 Existing Brownfield Run-Off Rates

The existing surface water runoff rate from the site has been calculated using the Rational Method for direct runoff.

$$Q = 2.78CiA$$

Where:

Q = Maximum flow rate (l/s)

C = runoff coefficient

i = Rainfall Intensity (mm/hr)

A = Catchment Area (Ha)

The runoff coefficient for the area considered in the calculation has been taken as 1.0.

The rainfall intensity adopted in the calculation is 50 mm/hr.

Based on the existing drained area plan (Appendix E), the Catchment Area is 1.98 Ha.

The existing runoff rate for the site is therefore 275.5 l/s.

3.3 Existing Greenfield Run-Off Rates

As a comparison, the greenfield run-off for the site area has been considered. This has been calculated using the ICP SUDS method in InfoDrainage (Appendix F). The rates presented below are what would be typical of a site with an equivalent area which remains undeveloped / covered in grass or vegetation.

The existing site is partly developed and therefore an urbanised catchment ratio of 0.46 has been adopted in the calculations. This value is based on the proportion of the site that is currently developed according to the existing drained area plan within Appendix E.

The equivalent greenfield run-off rate is tabled below: -

RETURN PERIOD	$Q_{\text{GREENFIELD}}$ (l/s)
1 in 1-year	51.9
1 in 2-year	58.8
1 in 30-year	91.8
1 in 100-year	103.7
Q_{bar}	59.7

Table 3.2 – Greenfield Run-off Rates

3.4 Proposed Surface Water Discharge Rate

The non-Statutory Technical Standards for Sustainable Drainage Systems (2015) states that for greenfield developments, the peak runoff rate from the development to any highway drain, sewer or surface water body for the 1 in 1-year and 100-year rainfall events should never exceed the peak greenfield runoff rate for the same event. For developments which were previously developed (brownfield), the peak runoff rate from the development to any drain, sewer or surface water body for the 1 in 1-year and 1 in 100-year rainfall events must be as close as reasonably practicable to the greenfield runoff rate from the development for the same rainfall event but should never exceed the rate of discharge from the development prior to redevelopment for that event.

As set out within the Bury Council SFRA, developments should aim to restrict the runoff rate from site to *greenfield run-off rate where feasible*.

It is proposed that the discharge rate from site is limited to a maximum of QBAR, 59.7 l/s, for all storm events up to the 1 in 100-year storm with an allowance for climate change.

Restricting the run-off to this rate would result in an 78.3% betterment from the existing run-off rates which complies with the requirements outlined in the Non-Statutory Technical Standards for Sustainable Drainage noted above.

3.5 Attenuation Requirements

The proposed development results in approximately 21890m² of impermeable area.

The post development discharge rates will include for an increase in the rainfall intensity of 40% and 45% for the 1 in 30-year and 1 in 100-year storm events respectively to allow for climate change. This is consistent with a design life for the development of 100 years, as outlined by the National Planning Practice Framework (NPPF).

A quick storage estimate for the 1 in 100 year +45% allowance for climate change InfoDrainage, indicates that the approximate attenuation volumes shown in table 3.4 are required to limit the peak surface water discharge to 59.7 l/s. The InforDrainage calculations can be seen in Appendix G.

RETURN PERIOD	DEVELOPMENT AREA (ha)	SURFACE WATER ATTENUATION ESTIMATE (m ³)
1:100 Year +45% CC	2.189	993-1503

Table 3.4 – Surface Water Attenuation Estimate

4.0 SURFACE WATER DISCHARGE & SUDS ASSESSMENT

4.1 Surface Water Discharge Assessment

In accordance with NPPF, the following hierarchy of surface water drainage options has been considered:

- Discharge into the ground (infiltration);
- Discharge to a surface water body;
- Discharge to a surface water sewer, highway drain, or another drainage system;
- Discharge to a combined sewer.

Infiltration has been considered. Due to the potential contamination risk posed given the presence of made ground on site, the limited infiltration rates, and elevated ground water levels in some locations, infiltration has been discounted as the primary method of discharging surface water from the site. Localised areas of infiltration are being proposed at this stage, however further site investigation will be required to confirm the feasibility.

Opportunities for discharge to a watercourse have been considered. The closest named watercourse is the Manchester, Bolton & Bury Canal which lies immediately to the northwest of the site. The topography of the site is such that the drainage network would be too deep at the point of connection for this to be a suitable discharge point. Bury Council have confirmed that a culverted watercourse flows beneath the southern portion of the site from west to east. Pre-planning advice has been sought from Bury Council LLFA to understand any of their requirements for the surface water drainage network to be connected into the culvert.

Surface water discharge rates from the site are to be restricted to QBAR for the 100-year storm event. Refer to the Outline Drainage Strategy for the Micro-Drainage outputs and initial storage estimate calculations.

Foul water flows will be collected by a dedicated gravity network designed in accordance with BS EN 752 before discharging to the existing combined drainage on site. The connectivity of the existing combined drainage network on site into the public sewer network will need to be confirmed with a CCTV survey. The foul connection will also be subject to agreement under Section 106 of the Water Industry Act.

4.2 Sustainable Urban Drainage

Table 4.1 below provides a summary of typical SuDS techniques outlined within the CIRIA C753 SuDS manual. Based on a review of the suitability of SuDS techniques it is proposed that the development may incorporate the following:

SUDS TECHNIQUE	DESCRIPTION	SUITABILITY FOR DEVELOPMENT SITE	
Rainwater Harvesting	Collection of rainwater run-off for use	Not suitable due to limited potential use for rainwater	✗
Soft Landscaping	Grassed areas that allow direct infiltration of rainwater	Suitable	✓
Filter Drains	Linear drains / soakaways with either granular fill and perforated pipe, or dense vegetation that treat runoff from adjacent impermeable areas	Possibly suitable in localised areas – subject to further site investigation works	?
Swales	Shallow landscape channel that can infiltrate or convey runoff.	Possibly suitable in localised areas – subject to further site investigation works	?
Infiltration Basins	Depressions in the ground designed to store and infiltrate runoff to the ground. Can be landscaped to provide amenity value.	Possibly suitable in localised areas – subject to further site investigation works	?
Wet Ponds	Basins with permanent pool of water providing water quality treatment, wildlife, and amenity benefit.	Not suitable due to safety adjacent to school site	✗

	Designed to provide temporary storage for additional runoff.		
Extended Detention Basins	Dry basins that are designed to temporarily store runoff providing water quality treatment.	Suitable to provide a mechanism for partial infiltration – subject to further site investigation works	?
Constructed Wetland	Ponds and shallow wetland areas with vegetation to improve pollution removal and enhance wildlife habitat.	Not suitable due to limited space	×
Porous Paving	Granular build-up beneath permeable paving systems that can be used to either store runoff (lined system) and increase time of concentration or allow percolation into the ground.	Type B system suitable to car park area – subject to further site investigation works	?
Trees Pits	Managed permeable paving systems around tree pits that can be used to either store runoff (lined system) and increase time of concentration or allow percolation into the ground.	Suitable	✓
Soakaways	Infiltration device to temporarily store runoff and allow it to percolate into the ground.	Suitable to provide a mechanism for partial infiltration – subject to further site investigation works	?
Green Roof	Vegetated roof area that reduces runoff and increases time of concentration.	Bio-solar roof provided but not utilised for storage due to architectural constraints	×
Blue Roof	Roof area designed to store and reduce peak runoff rates during intense storms.	Not suitable due to architectural constraints	×
Underground Storage	Attenuation structures installed below ground to provide runoff storage.	Suitable within soft landscaping to the east of the site	✓

× Not suitable

? Potentially suitable subject to further investigation

✓ Suitable

Table 4.1 – SUDs Techniques & Suitability for Development Site

4.3 Water Quality Assessment

The drainage from the site is from the roof and hard paving areas. Water quality is generally affected by frequent rainfall events (1 in 1-year events or less), which is circa 5mm/hr for the proposed development site. To assess the water quality, consideration will be given to the guidance within the National Standard for Sustainable Urban Drainage (NSSUD) and CIRIA Guide C753. The pollution hazard levels for different land uses are presented in table 4.2 and are based on the definitions in the NSSUD and C753.

POLLUTION HAZARD LEVEL	LAND USE
Very Low	Residential roofs
Low	Individual property driveways, non-residential roofs, residential car parks, low traffic roads, non-residential car parking with infrequent change (e.g. Schools, offices)
Medium	Commercial yards and delivery areas, non-residential car parking with frequent change (e.g. hospital, retail), minor roads
High	Site with heavy pollution (e.g. Haulage yards, lorry parks, waste sites, sites with chemical and fuels are delivered, handled, stored etc.)

Table 4.2 – Pollution Hazard Levels

The pollution hazard level is low based on Table 4.2 with the primary consideration given to removal of gross solids and sediment.

The following tables indicate the minimum number of treatment stages required before surface run-off should reach the infiltration or receiving water body and are extracted from the NSSUD.

POLLUTION HAZARD LEVEL	LAND USE	LOW	MEDIUM	HIGH
G1	Source Protection Zone 1, within 50m of a well, spring or borehole that supplies potable water.	1	3	Consult the EA
G2	Into or immediately adjacent to a sensitive receptor that could be influenced by infiltrated water. Includes designated nature conservation, heritage, and landscape sites – including Biodiversity Action Plan (BAP) habitats and Protected Species.	1	3	
G3	Source Protection Zone II and III or Principal Aquifer	1	3	
G4	Secondary Aquifer	1	2	
G5	Unproductive strata	1	2	

Table 4.3 – Groundwater Minimum Treatment Stages

POLLUTION HAZARD LEVEL	NORMAL SURFACE WATER	SENSITIVE SURFACE WATER
Low	0	1
Medium	2	3
High	Consult the EA	

Table 4.4 – Surface Water Body Minimum Treatment Stages

Infiltration is potentially viable in localised areas and discharge into the secondary aquifer will require 1 level of treatment for a low pollution level.

Discharge of surface water to the receiving culverted watercourse will require no treatment stages due to the low pollution hazard level. However, the adoption of SuDS, sumps and good practice will provide inherent treatment to improve the water quality of the runoff.

External areas will pass through silt traps/sumps prior to entering the attenuation and flow control devices. The silt traps and sumps will allow most of the sediment and solids to settle out under low flows, prior to discharging to the culvert.

5.0 OUTLINE DRAINAGE STRATEGY

Refer to Appendix I for the general arrangement drawing of the proposed below ground drainage strategy.

5.1 Surface Water System

The development will have a dedicated surface water network that will collect the rainwater from the proposed building and hard standing areas. The network will then discharge under gravity to the culverted watercourse running across the site subject to agreement with Bury Council LLFA.

The surface water discharge from the site is to be limited to the rate detailed within Section 3.2 of this report using a flow control device within the final manhole of the network prior to discharging into the culvert. Proposed discharge rates are to be confirmed with Bury Council LLFA and United Utilities as part of the detailed design.

Attenuation will be provided in the form of permeable surfacing build-ups and a detention basin. It should be noted that the drainage of the pitches has been designed to fully infiltrate, however this will be subject to further infiltration testing and at this stage they have been included in the overall impermeable area figure.

The surface water drainage network is to be designed in accordance with Building Regulations Part H, BS EN 752 and Code for Adoption. In addition, the following requirements will also be adopted in accordance with the Non-Statutory Technical Standards for Sustainable Drainage: Practice Guidance:

- The below ground drainage system will be designed to ensure flooding does not occur on site for the 1 in 30-year rainfall event with no internal flooding for the 1 in 100-year rainfall event.
- The surface water system is to be designed to accommodate the 1-, 2-, 30- and 100-year rainfall events with an increase in the rainfall intensity of 40% and 45% for the 1 in 30-year and 1 in 100-year storm events respectively to allow for climate change. The system will be designed for a maximum storm duration of 6 hours.

Based on initial comments from Manchester Metrolink, all drainage and associated surface finishes adjacent to the Metrolink line to the east of the site will be designed to fall away from the embankment to prevent any impacts on its stability.

5.2 Foul Water System

The site will have a dedicated foul water network that will collect the foul water associated with the development before connecting into the existing combined network in the southern part of the site.

The combined drainage connection will be subject to further survey work to confirm connectivity with the public sewer and a Section 106 application with United Utilities.

The drainage system is to be designed in accordance with Building Regulations Part H, BS EN 752 and Codes for Adoption.

5.3 Phasing & Surface Water Management During Construction

The development is intended to be delivered in a single phase.

Surface water management during construction will be addressed by the Main Contractor as part of their 'Construction Management Plan'.

A brief overview of the key considerations relating to surface water management and flood risk that will need to be incorporated into the Main Contractor's construction methodology include:

- Subject to the level of contamination beneath the site and site remediation required, as well as the quality of working platform compaction to reduce infiltration, consideration should be given to the risk of residual contamination on site affecting groundwaters and adjacent watercourses.
- The risk of diesel spillage and other contamination risk during construction activities are to be assessed and measures implemented to ensure they do not cause a risk to groundwaters and the adjacent watercourse.

6.0 FUTURE MANAGEMENT & MAINTENANCE

The proposed drainage solution uses SuDS techniques in accordance with the CIRIA SUDS Manual C753. The following SuDS features have been adopted in the drainage strategy for Star Radcliffe Academy:-

- Permeable Paving
- Extended Detention Basin
- Soft Landscaping
- Tree Pits
- Inspection chambers, manholes and catchpits.
- Pipes.
- Drainage channels and gullies.
- Flow control device

A suitable maintenance strategy should be adopted to ensure the drainage network is cleaned regularly and the routine maintenance and cleansing regime should be documented.

The Main Contractor delivering the development is to update the general requirements to reflect the product specific requirements of the as-installed proprietary SuDS and incorporate these into the Operation & Maintenance Manual for the building.

The Main Contractor should provide a Verification Report, including photographic evidence, to demonstrate that the drainage has been constructed as per the design drawings. As-built drawings should be supplied by the Main Contractor where the drainage varies from the construction drawings.

The maintenance of the specified SuDS should be detailed in accordance with the CIRIA SuDS Manual C753, as per the operation and maintenance guidance outlined below.

6.1 General Maintenance & Inspection Requirements

No work shall be carried out on the drainage system without permission from a nominated person, who has access to information/a working knowledge of the system.

Maintenance/inspection work shall be carried out in a safe/planned manner.

All work is to be carried out by competent persons suitably trained and equipped in accordance with current statutory safe working policies.

Entry into confined spaces shall be kept to a minimum and be restricted to suitably qualified/equipped personnel working in accordance with current statutory safe working policies.

Drainage systems shall be inspected on a regular basis or when any problems arise. Any debris/defects discovered shall be recorded and a programme of cleaning/ repair initiated. Urgent repairs/cleaning shall be actioned as soon as practicable.

It is recommended that the drainage system is inspected a minimum of twice a year, with the system also being inspected after all major storm events.

Clearing of the drainage system can be achieved by a number of methods depending on the nature of the work;

- Rodding – manual/mechanical with flexible rods.
- Jetting – high-pressure water jetting.
- Plunging.

6.2 Inspection Chambers, Manholes and Catchpits

The appropriate health and safety equipment must be used when accessing manholes/catchpits. Confined space certificates must be held by any personnel entering a manhole and the appropriate permits should be obtained from the Maintenance Manager prior to any access. The following operations should be carried out annually:

- Covers of inspection chambers and manholes shall be removed and the sides, benching and channels cleared.
- Deposits of silt in inspection chambers, catchpits and manholes shall be removed. Any traps shall then be plunged and thoroughly flushed out with clean water. This should be completed in Autumn, after leaf fall has halted.
- Main and branch drains shall be cleared as required and afterwards be flushed with clean water. Any obstructions found shall be removed and not flushed down the system.
- Covers of inspection chambers, manholes and catchpits shall be replaced, bedded in suitable sealing material as required and bolted/locked down as appropriate. Missing bolts and broken items shall be replaced in accordance with the manufacturer's details.

6.3 Pipes

Regular inspection and maintenance are important to identify areas which may have become obstructed/clogged and may not be draining correctly, failure to do so would expose the development to flood risk.

Pipes are proprietary products and therefore the materials used can vary across the site. As such, the manufacturer's recommendations should be followed. Access for maintenance of the pipes is provided through inspection chambers and manholes.

6.4 Drainage Channels and Gullies

Channels and gullies should be inspected and cleaned in accordance with the manufacturer's details. Channel units can be cleaned using a high-pressure hose; this can be fed into the channel system through access units strategically placed along the channel run. The throat section of channel units should always be kept clear to ensure uninterrupted flow of surface water into the drainage channel and any debris within the throat should be removed.

Locking bolts should be replaced and sufficiently tightened, taking care that the bolt heads do not stand above the top surface of the cover or grate. If covers are allowed to move within their frame, this may cause damage to the frame or seating. The below table sets out the maintenance schedule for the drainage channel and gully components of the proposed drainage systems.

MAINTENANCE SCHEDULE	REQUIRED ACTION	TYPICAL FREQUENCY
Regular Maintenance	Litter and debris removal.	Monthly or as required.
	Check and remove large debris and/or vegetation growth near pipe runs.	Monthly or as required.
	Inspect for evidence of poor operation and/or weed growth. If required, take remedial action. Inspect silt accumulation rates and establish appropriate brushing frequencies.	Monthly for 3 months, then six monthly intervals. Also, 48 hours after large storms.
Remedial Actions	Inspect access/outlet boxes and rod through poorly performing channels and outlets as initial	As required.

	remediation.	
	Seek advice as to remediation techniques suitable for the type of performance issue.	As required, if above actions do not improve performance.
Monitoring	Initial inspection including channel outlet boxes and gully sumps.	Monthly for 3 months, then six monthly intervals. Also, 48 hours after large storms.

6.5 Flow Control Device

Regular inspection and maintenance are important, to identify if the vortex flow control device has become obstructed/clogged and may not be functioning correctly, as failure to do so would expose the development to a risk of flooding.

Vortex flow control devices are proprietary products and therefore can vary from manufacturer to manufacturer. As such, the manufacturer's recommendations should be followed. Normally, little maintenance is required as a vortex flow control device has no moving parts.

If blockages occur, they tend to do so at the intake of the vortex flow control device.

Vortex flow control devices are generally fitted with a pivoting by-pass door, which allows the manhole chamber to be drained down should blockages occur.

The smaller conical units, below the minimum recommended size, are also supplied with rodding facilities or vortex suppressor pipes as standard.

Following installation of the vortex flow control device it is vitally important that any building materials etc. are removed from the unit and the chamber.

After the system is made fully functional, it is recommended that each unit be inspected monthly for three months and thereafter at six monthly intervals with hose down if required. Units should also be inspected within 48 hours after large storms.

6.6 Permeable Pavements

Regular inspection and maintenance are important for the effective operation of pervious pavements. Maintenance responsibility for a pervious pavement and its surrounding area should be placed with an appropriate responsible organisation. Before handing over the pavement to the client, it should be inspected for clogging, litter, weeds and water ponding, and all failures should be rectified after handover, the pavement should be inspected regularly, preferably during and after heavy rainfall to check effective operation and to identify any areas of ponding.

MAINTENANCE SCHEDULE	REQUIRED ACTION	TYPICAL FREQUENCY
Regular Maintenance	Brushing and vacuuming (standard cosmetic sweep over the whole surface)	Once a year, after autumn leaf fall, or reduced frequency as required, based on site specific observations of clogging or manufacturers recommendations – pay particular attention to areas where water runs onto pervious surface from adjacent impermeable areas as this area is most likely

		to collect the most sediment.
Occasional Maintenance	Stabilise and mow contributing and adjacent areas	As required.
	Removal of weeds or management using glyphosate applied directly into the weeds by an applicator rather than spraying.	As required – once per year on less frequently used pavements.
Remedial Actions	Remediate any landscaping which, through vegetation maintenance or soil slip, has been raised to within 50mm of the level of the paving	As required
	Remedial work to any depressions, rutting and cracked or broken blocks considered	As required
	Rehabilitation of surface and upper substructure by remedial sweeping.	Every 10 to 15 years or as required (if infiltration performance is reduced due to significant clogging)
Monitoring	Initial inspection	Monthly for three months after installation
	Inspect for evidence of poor operation and/or weed growth – if required, take remedial action.	Three-monthly, 48 h after large storms in first six months.
	Inspect silt accumulation rates and establish appropriate brushing frequencies	Annually
	Monitor inspection chambers	Annually

6.7 Extended Detention Basin

Maintenance responsibilities for a basin should always be placed with an appropriate organisation. Adequate access should be provided to all detention basin areas for inspection and maintenance, including for appropriate equipment and vehicles. Litter and debris removal should be undertaken as part of general landscape maintenance for the site and before any other SuDS management task. All litter should be removed from the site.

The maintenance requirements for detention basins are outlined within Table 13.2 of the CIRIA SUDS Manual C753. A copy of that table is replicated below to set out the maintenance schedule for the cellular attenuation tank component of the proposed drainage systems.

Maintenance Schedule	Required Action	Typical Frequency
Regular Inspections	Remove litter and debris	Monthly
	Cut grass – for spillways and access routes	Monthly (during growing season), or as required
	Cut grass – meadow grass in and around basin	Half yearly (spring – before nesting season, and autumn)
	Manage other vegetation and remove nuisance plants	Monthly (at start, then as required)
	Inspect inlets, outlets and overflows for blockages, and clear if required.	Monthly
	Inspect banksides, structures, pipework etc for evidence of physical damage	Monthly
	Inspect inlets and facility surface for silt accumulation. Establish appropriate silt removal frequencies.	Monthly (for first year), then annually or as required
	Check any penstocks and other mechanical devices	Annually
	Tidy all dead growth before start of growing season	Annually
	Remove sediment from inlets, outlet and forebay	Annually (or as required)
	Manage wetland plants in outlet pool – where provided	Annually
Occasional Maintenance	Reseed areas of poor vegetation growth	As required
	Prune and trim any trees and remove cuttings	Every 2 years, or as required
	Remove sediment from inlets, outlets, forebay and main basin when required	Every 5 years or as required (likely to be minimal requirements where effective upstream source control is provided)
Remedial actions	Repair erosion or other damage by reseeding or re-turfing	As required
	Realignment of rip-rap	As required
	Repair/rehabilitation of inlets, outlets and overflows	As required
	Relevel uneven surfaces and reinstate design levels	As required

6.8 Tree Pits

Maintenance requirements of trees will be greatest during the first few years, when the tree is becoming established. Early maintenance should involve regular inspection, removal of invasive vegetation and possible irrigation during long dry periods, particularly in soils with high void ratios. Tree roots need to establish good root-soil contact before they can efficiently


extract water from the soil. The expertise of an arboriculturist/landscape architect with local knowledge should be sought regarding appropriate irrigation schedules. Maintenance responsibility for a tree pit or planter should always be placed with an appropriate organisation.

The maintenance requirements for tree pits are outlined within Table 19.3 of the CIRIA SUDS Manual C753. A copy of that table is replicated below.

Maintenance Schedule	Required Action	Typical Frequency
Regular Inspections	Remove litter and debris	Monthly
	Manage other vegetation and remove nuisance plants	Monthly (during growing season), or as required
	Inspect inlets and outlets	Half yearly (spring – before nesting season, and autumn)
Occasional Maintenance	Check tree health and manage tree appropriately	Annually
	Remove silt build-up from inlets and surface and replace mulch as necessary	Annually, or as required
	Water	As required (in periods of drought)
Remedial actions	Inspect silt accumulation rates and establish appropriate removal frequencies	Half yearly

APPENDIX A
Existing Topographical and Utilities Survey Information

APPENDIX B
United Utilities Sewer Records



United Utilities Maps for SafeDig

Date :	18/01/2022 09:54:12
Centre X:	378736
Centre Y:	407606
Scale :	2000
UserName:	MOTTMACNRT

Extract from maps of United Utilities' Underground Assets

The position of the underground apparatus shown on this plan is approximate only and is given in accordance with the best information currently available. The actual positions may be different from those shown on the plan and private service pipes may be shown by a blue broken line. United Utilities Water will not accept liability for any damage caused by the actual position being different from those shown.


Crown copyright and database rights 2020. Ordnance Survey 100022432 This plan is based on the Ordnance Survey Map with the sanction of the Controller of H.M. Stationary Office. Crown and United Utilities Water copyrights are reserved. Unauthorised reproduction will infringe these copyrights.



APPENDIX C
Proposed Development Plans



P12	Drawing error - re-placed at S4	16.08.23	BT	IK
P11	Issued as S4 - LAP Authorisation	11.08.23	BT	IK
P10	Changing room layout amended and hygiene room added	03.07.23	BT	IK
P09	Issued for Stage 3	04.08.23	BT	IK
P08	Updated for CEM4a	24.07.23	BT	IK
P07	Kitchen layout updated to latest information	21.07.23	BT	IK
P06	Updated following CEM 4	12.07.23	BT	IK
P05	Issued for final comment	08.07.23	SH	IK
P04	WIP-issue following Academy comments	04.07.23	SH	IK
P03	Updated to incorporate steel frame	29.06.23	SH	IK
P02	Updated following CEM 3	27.06.23	SH	IK
P01	Stacks added to the back of classrooms	05.06.23	SH	IK
Rev	Description	Date	Cr	App
Rev			by	
SH		09/29/22	IK	



T +44(0)161 8287900
E manchester@ahr.co.uk
www.ahr.co.uk

client name	Department for Education
project	Star Academy Radcliffe
drawing	Ground Floor + Sports
computer file	Radcliffe Star Academy Radcliffe\103\AHR\22\02-BA-001.rvt
project number	2023.00187.000
drawing number	FS1013-AHR-01-00-D-A-2001
scale	1:100
rev	P12
issue status	S4
This drawing is to be used in conjunction with all related drawings. All dimensions must be checked and verified on site before commencing any work or producing shop drawings. The engineer should be notified immediately of any discrepancy. This drawing is copyright and remains the property of AHR.	

Area Schedule (Gross Internal Area)		
Level	Name	Area
LEVEL 00	Ground	2801.68 m ²
LEVEL 01	First	1510.19 m ²
LEVEL 02	Second	1704.48 m ²
Grand total: 3		6016.35 m ²



P09	Issued as S4 - LAP Authorisation	11.08.23	BT	IK
P08	Corridor to IT Server room updated	31.07.23	BT	IK
P07	Issued for Stage 3	04.08.23	BT	IK
P06	Updated following CEM 4	12.07.23	BT	IK
P05	Issued for final comment	06.07.23	SH	IK
P04	WIP issue following Academy comments	04.07.23	SH	IK
P03	Updated to incorporate steel frame	29.06.23	SH	IK
P02	Updated following CEM 3	27.06.23	SH	IK
P01	Stacks added to the back of classrooms	05.06.23	SH	IK
Rev	Description	Date	Dr	App
SH		09/29/22	IK	

AHR
AHR Architects Ltd
5th Floor
55 Princess Street
Manchester
M2 4EW
United Kingdom

T +44(0)161 8287900
E manchester@ahr.co.uk
www.ahr.co.uk


client name	DfE
project	Radcliffe Leadership Academy
drawing	First Floor
computer file	Autodesk Docs\Star Academy Radcliffe\FS1013-AHR-ZZ-XX\A5-A-0001.rvt
project number	2023.00187.000
drawing number	FS1013-AHR-01-01-D-A-2002
scale	1 : 100
rev	P09
issue status	S4

This drawing is to be read in conjunction with all related drawings. All dimensions must be checked and verified on site before commencing any work or producing shop drawings. The originator should be notified immediately of any discrepancy. This drawing is copyright and remains the property of AHR.




1 Level 02 - GA Plan - Sheet 1
1 : 100

P09	Issued as S4 - LAP Authorisation	11.08.23	BT	IK
P08	Drawing number updated	31.07.23	BT	IK
P07	Issued for Stage 3	04.08.23	BT	IK
P06	Updated for CEM4s	24.07.23	BT	IK
P05	Issued for final comment	06.07.23	SH	IK
P04	WIP issue following Academy comments	04.07.23	SH	IK
P03	Updated to incorporate steel frame	29.06.23	SH	IK
P02	Updated following CEM 3	27.06.23	SH	IK
P01	Stacks added to the back of classrooms	05.06.23	SH	IK
Rev	Description	Date	Dr by	App by
original by		date created		approved by
SH		09/29/22		IK



T +44(0)161 8287900
E manchester@ahr.co.uk
www.ahr.co.uk

client name	DfE
project	Radcliffe Leadership Academy
drawing	Second Floor
computer file	Autodesk Docs\Star Academy Radcliffe\FS1013-AHR-ZZ-XX-MS-A-0001.rvt
project number	2023.00187.000
drawing number	FS1013-AHR-01-02-D-A-2002
scale	1 : 100 @A1
rev	P09
issue status	S4
This drawing is to be read in conjunction with all related drawings. All dimensions must be checked and verified on site before commencing any work or producing shop drawings. The originator should be notified immediately of any discrepancy. This drawing is copyright and remains the property of AHR.	



P04	Issued as SA - LAP Authorisation	11.08.23	BT	IK
P03	Issued for Stage 3	04.08.23	BT	IK
P02	Rooflights to sports hall removed in line with CEM 4.000.2.4	21.07.23	BT	IK
P01	Updated following CEM 4	12.07.23	BT	IK
Rev	Description	Date	Dr	App
BT		10/03/22	Approver	

AHR Architects Ltd
5th Floor
55 Princess Street
Manchester
M2 4EW
United Kingdom

T +44(0)161 8287500
E manchester@ahr.co.uk
www.ahr.co.uk

client name	DIE
project	Radcliffe Leadership Academy
drawing	Roof Plan
computer file	Radcliffe Leadership Academy\FS1013-AHR-22-03-MS-A-001.rvt
project number	2023.00187.000
drawing number	FS1013-AHR-01-RF-D-A-2003
scale	1 : 100
rev	P04
issue status	S4
This drawing is to be read in conjunction with all related drawings. All dimensions must be checked and verified on site before commencing any work or producing shop drawings. The originator should be notified immediately of any discrepancy. This drawing is copyright and remains the property of AHR.	

APPENDIX D
Existing Impermeable Areas Plan



- NOTES:**
1. THIS DRAWING IS INTENDED TO INDICATE THE EXISTING DRAINED AREAS FROM THE STAR RADCLIFFE ACADEMY DEVELOPMENT. IT IS BASED UPON A REVIEW OF THE TOPOGRAPHICAL SURVEY AND AERIAL IMAGES OF THE SITE.
 2. FOR THE TOPOGRAPHICAL SURVEY, REFER TO GREENHATCH DRAWING FS1013-GHG-XX-XX-D-U-0002.
 3. EXISTING DISCHARGE RATES GIVEN HAVE BEEN CALCULATED USING MICRODRAINAGE. BROWNFIELD RUN-OFF RATES ARE BASED ON THE HARD PAVED AREAS.

KEY	
	PLANNING BOUNDARY
	DEVELOPMENT BOUNDARY TOTAL AREA: 45620m ² (4.562ha)
	SOFT LANDSCAPING AREA TOTAL AREA: 25800m ² (2.58ha)
	HARD LANDSCAPING AREA TOTAL AREA: 19820m ² (1.982ha)

GREENFIELD RUN-OFF RATES	
EVENT	GREENFIELD RUN-OFF
1:1	51.9 l/s
1:2	58.8 l/s
1:30	91.8 l/s
1:100	103.7 l/s
Q _{50%}	59.7 l/s

GREENFIELD RUN-OFF CALCULATED IN MICRODRAINAGE USING SOURCE CONTROL

P03	COMMENTS INCORPORATED	08.09.23	HW	PW
P02	STAGE 3 ISSUE	10.08.23	SA	PW
P01	ISSUED FOR PLANNING	08.06.23	HW	PW

Rev.	Description:	Date:	By:	Chkd:
------	--------------	-------	-----	-------



Project:
STAR RADCLIFFE ACADEMY

Drawing Title:
EXISTING DRAINED AREAS

Status:
STAGE 3

Size:	Date:	Drawn by:	Designed by:	Checked by:
A1	JUN 23	HW	--	PW

Scale:	Project No:
1:500	2303-02

Project:	Originator:	Volume:	Level:	Type:	Role:	Category/Number:	Rev:
----------	-------------	---------	--------	-------	-------	------------------	------

FS1013-REN-EX-00-D-C-5200-P02

APPENDIX E
InfoDrainage Greenfield Run-off Rates

UK and Ireland Rural Runoff Calculator
×

ICP SUDS / IH 124	ADAS 345	FEH	ReFH2	Greenfield Volume
-------------------	----------	-----	-------	-------------------

Method ☒ ICP SUDS ☐ IH 124

Area (ha)

SAAR (mm) Map

Soil

Region ...

Additional Options

Urban

Return Period (years)

Growth Curve


Calculate

Results

Region	QBAR Rural (L/s)	QBAR Urban (L/s)	Q 2 (years) (L/s)	Q 1 (years) (L/s)	Q 30 (years) (L/s)	Q 100 (years) (L/s)
Region 10	34.8	59.7	58.8	51.9	91.8	103.7

OK
Cancel
 Help

APPENDIX F
Proposed Impermeable Areas Plan



- NOTES:
- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH:
 - EXISTING IMPERMEABLE AREA PLAN
 - PROPOSED BELOW GROUND DRAINAGE DRAWING
 - MICRODRAINAGE MODEL AND CALCULATION OUTPUTS

PLANNING BOUNDARY

DEVELOPMENT BOUNDARY

PROPOSED IMPERMEABLE AREA SUMMARY		
MANHOLE	HATCH	AREA (ha)
S1.00	A	0.383
S1.01	B	0.105
S1.02	C	0.095
S2.00	D	0.103
S3.00	E	0.020
S1.06	F	0.081
S4.00	G	0.016
S4.01	H	0.017
S4.04	I	0.187
S3G PITCH	J	0.585
S3G MUGA	K	0.174
S2G PITCH	L	0.320
S5.00	M	0.028
S5.01	N	0.063
S6.00	N	0.012
TOTAL		2.189

SITEWIDE TOTAL AREA	
HATCH	AREA (ha)
IMPERMEABLE AREA	2.189
PERMEABLE AREA	2.373
TOTAL	4.562

P02	ISSUED FOR PLANNING	07.09.23	HW	PW
P01	STAGE 3	10.08.23	SA	PW
Rev:	Description:	Date:	By:	Chkd:



Renaissance Associates Ltd
Carvers Warehouse
77 Dale Street
Manchester
M1 2HG

Project:

STAR RADCLIFFE ACADEMY

Drawing Title:

PROPOSED DRAINED AREAS
PLAN

Status:

STAGE 3

Size:	Date:	Drawn by:	Designed by:	Checked by:
A1	AUG'23	SA	SA	PW

Scale:	1:500	Project No:	2303-02
Project - Originator - Volume - Level - Type - Role - Number - Revision:			

FS1013-REN-EX-00-D-C-5201

P02

APPENDIX G
InfoDrainage Quick Storage Estimate

Quick Storage Estimate

Input

Input Type

User Input

Area (ha)

2.189

Volumetric Runoff Coefficient

1.000

Discharge Rate (L/s)

59.7

Infiltration Rate (m/hr)

0.0

Safety Factor

2.0

Quick

Calculate

Create New

From Library

All

FSR

...

Method

FSR

Number of Storms

38

Max. Run Time (mins)

20160

Input

Results

2D Graph

Create New

Help

Quick Storage Estimate

Results

Quick Storage Estimate variables require approximate storage of between 993m³ - 1503m³.

These values are estimates only and should not be used for final design purposes.

Input


Results

2D Graph

Create New

Help

APPENDIX H
Below Ground Drainage GA



FOR PROPOSED SITE LEVELS AND CHANNEL / GULLY LOCATIONS, REFER TO LANDSCAPE ARCHITECT'S DRAWINGS.

ALL CONNECTIONS BETWEEN ABOVE GROUND DRAINAGE AND BELOW GROUND DRAINAGE TO BE SIZED TO SUIT ABOVE GROUND DRAINAGE.

ALL DRAINAGE AND SURFACE FINISHES ADJACENT TO THE METROLINK LINE TO THE EAST OF THE SITE ARE TO FALL AWAY FROM THE EMBANKMENT TO PREVENT ANY IMPACTS ON ITS STABILITY.

ITCHES DESIGNED TO BE DRAINED VIA AN INFILTRATION ONLY SYSTEM. THE
EASIBILITY OF THIS IS TO BE CONFIRMED WITH FURTHER INFILTRATION
ESTING HOWEVER AT THIS STAGE AREAS HAVE BEEN ALLOWED FOR IN THE
MODEL.



renaissance

Renaissance Associates Ltd
Carvers Warehouse
77 Dale Street
Manchester
M1 2HG


Drawing Title:

*BELOW GROUND DRAINAGE
PLAN*

Size:	Date:	Drawn by:	Designed by:	Checked by:
A1	AUG'23	SA	SA	AI

Scale:	1:500	Project No:	2303-02
Project - Originator - Volume - Level - Type - Role - Number:			Revision:

FS1013-REN-EX-00-D-C-5210 | P02

- | | |
|---|---|
|  | PLANNING BOUNDARY |
|  | DEVELOPMENT BOUNDARY |
|  | PROPOSED SURFACE WATER DRAINAGE
(150mm DIAMETER UNO) |
|  | PROPOSED FOUL WATER DRAINAGE
(100mm DIAMETER UNO) |
|  | EXISTING SURFACE WATER CULVERT |
|  | EXISTING COMBINED SEWER |
|  | RODDING EYE |
|  | GULLY TO LANDSCAPE ARCHITECTS SPECIFICATION UNO |
|  | CHANNEL DRAIN TO LANDSCAPE ARCHITECTS SPECIFICATION UNO |
|  | RAINWATER PIPE / SOIL VENT PIPE |
|  | PROPOSED SURFACE WATER MANHOLE |
|  | PROPOSED SURFACE WATER MANHOLE
w/FLOW CONTROL DEVICE |
|  | PROPOSED FOUL WATER MANHOLE |
|  | ATTENUATION WITHIN 2G PITCH BUILD-UP |
|  | ATTENUATION UNDER PERMEABLE PAVING |

APPENDIX J
Proposed Surface Water Micro Drainage Calculations

Renaissance Assoc.		Page 1
Carvers Warehouse 77 Dale Street Manchester M1 2HG		
Date 08/09/2023 11:33 File 230901 model.MDX	Designed by HenryWilkinson Checked by	
Innovyze		Network 2020.1.3

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	100	PIMP (%)	100
M5-60 (mm)	18.000	Add Flow / Climate Change (%)	0
Ratio R	0.360	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.933	4-8	1.240	8-12	0.015

Total Area Contributing (ha) = 2.189

Total Pipe Volume (m³) = 60.457

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	41.795	0.209	200.0	0.383	5.00	0.0	0.600	o	300	Pipe/Conduit	
S1.001	26.346	0.132	199.6	0.105	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.002	25.923	0.130	199.4	0.095	0.00	0.0	0.600	o	300	Pipe/Conduit	
S2.000	21.127	0.285	74.1	0.103	5.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	50.00	5.63	73.060	0.383	0.0	0.0	0.0	1.11	78.3	51.9
S1.001	50.00	6.02	72.851	0.488	0.0	0.0	0.0	1.11	78.4	66.1
S1.002	50.00	6.41	72.135	0.583	0.0	0.0	0.0	1.11	78.4«	78.9
S2.000	50.00	5.19	72.365	0.103	0.0	0.0	0.0	1.83	129.2	13.9

Renaissance Assoc.		Page 4
Carvers Warehouse 77 Dale Street Manchester M1 2HG		
Date 08/09/2023 11:33 File 230901 model.MDX	Designed by HenryWilkinson Checked by	
Innovyze		Network 2020.1.3

Area Summary for Storm


Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.383	0.383	0.383
1.001	-	-	100	0.105	0.105	0.105
1.002	-	-	100	0.095	0.095	0.095
2.000	-	-	100	0.103	0.103	0.103
1.003	-	-	100	0.000	0.000	0.000
1.004	-	-	100	0.000	0.000	0.000
3.000	-	-	100	0.020	0.020	0.020
1.005	-	-	100	0.000	0.000	0.000
1.006	-	-	100	0.081	0.081	0.081
1.007	-	-	100	0.000	0.000	0.000
4.000	-	-	100	0.016	0.016	0.016
4.001	-	-	100	0.017	0.017	0.017
4.002	-	-	100	0.000	0.000	0.000
4.003	-	-	100	0.000	0.000	0.000
4.004	-	-	100	0.187	0.187	0.187
4.005	-	-	100	0.000	0.000	0.000
5.000	-	-	100	0.174	0.174	0.174
5.001	-	-	100	0.000	0.000	0.000
6.000	-	-	100	0.585	0.585	0.585
6.001	-	-	100	0.000	0.000	0.000
5.002	-	-	100	0.000	0.000	0.000
1.008	-	-	100	0.000	0.000	0.000
7.000	-	-	100	0.320	0.320	0.320
1.009	-	-	100	0.000	0.000	0.000
1.010	-	-	100	0.000	0.000	0.000
1.011	-	-	100	0.000	0.000	0.000
8.000	-	-	100	0.028	0.028	0.028
8.001	-	-	100	0.063	0.063	0.063
9.000	-	-	100	0.012	0.012	0.012
1.012	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				2.189	2.189	2.189

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D, L (mm)	W (mm)
S1.012	S	70.160	63.862	0.000	0	0

Renaissance Assoc.		Page 5
Carvers Warehouse 77 Dale Street Manchester M1 2HG		
Date 08/09/2023 11:33 File 230901 model.MDX	Designed by HenryWilkinson Checked by	
Innovyze	Network 2020.1.3	
<u>Simulation Criteria for Storm</u> Volumetric Runoff Coeff 1.000 Additional Flow - % of Total Flow 0.000 Areal Reduction Factor 1.000 MADD Factor * 10m³/ha Storage 2.000 Hot Start (mins) 0 Inlet Coefficient 0.800 Hot Start Level (mm) 0 Flow per Person per Day (l/per/day) 0.000 Manhole Headloss Coeff (Global) 0.500 Run Time (mins) 60 Foul Sewage per hectare (l/s) 0.000 Output Interval (mins) 1 Number of Input Hydrographs 0 Number of Storage Structures 7 Number of Online Controls 3 Number of Time/Area Diagrams 0 Number of Offline Controls 0 Number of Real Time Controls 0 <u>Synthetic Rainfall Details</u> Rainfall Model FSR Profile Type Summer Return Period (years) 100 Cv (Summer) 1.000 Region England and Wales Cv (Winter) 0.840 M5-60 (mm) 18.000 Storm Duration (mins) 30 Ratio R 0.360		
©1982-2020 Innovyze		

Renaissance Assoc.		Page 7																								
Carvers Warehouse 77 Dale Street Manchester M1 2HG																										
Date 08/09/2023 11:33 File 230901 model.MDX	Designed by HenryWilkinson Checked by																									
Innovyze		Network 2020.1.3																								
<u>Porous Car Park Manhole: S2G Pitch, DS/PN: S7.000</u> <table> <tr> <td>Porosity</td> <td>0.50</td> <td>Slope (1:X)</td> <td>0.0</td> </tr> <tr> <td>Invert Level (m)</td> <td>69.470</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Width (m)</td> <td>10.0</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Length (m)</td> <td>392.4</td> <td>Cap Volume Depth (m)</td> <td>0.200</td> </tr> </table> <u>Tank or Pond Manhole: S1.10, DS/PN: S1.010</u> Invert Level (m) 68.297 <table> <thead> <tr> <th>Depth (m)</th> <th>Area (m²)</th> <th>Depth (m)</th> <th>Area (m²)</th> </tr> </thead> <tbody> <tr> <td>0.000</td> <td>180.0</td> <td>1.200</td> <td>552.0</td> </tr> </tbody> </table>			Porosity	0.50	Slope (1:X)	0.0	Invert Level (m)	69.470	Depression Storage (mm)	5	Width (m)	10.0	Evaporation (mm/day)	3	Length (m)	392.4	Cap Volume Depth (m)	0.200	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	0.000	180.0	1.200	552.0
Porosity	0.50	Slope (1:X)	0.0																							
Invert Level (m)	69.470	Depression Storage (mm)	5																							
Width (m)	10.0	Evaporation (mm/day)	3																							
Length (m)	392.4	Cap Volume Depth (m)	0.200																							
Depth (m)	Area (m ²)	Depth (m)	Area (m ²)																							
0.000	180.0	1.200	552.0																							
©1982-2020 Innovyze																										

Renaissance Assoc.		Page 8
Carvers Warehouse 77 Dale Street Manchester M1 2HG		
Date 08/09/2023 11:33 File 230901 model.MDX	Designed by HenryWilkinson Checked by	
Innovyze Network 2020.1.3		

1 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	7
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.360
Region	England and Wales	Cv (Summer)	1.000
M5-60 (mm)	18.000	Cv (Winter)	1.000

Margin for Flood Risk Warning (mm)	400.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON


Profile(s)

	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 10080
Return Period(s) (years)	1, 2, 30, 100
Climate Change (%)	0, 0, 0, 45

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	S1.00	15 Summer	1	+0%	1/15 Summer			
S1.001	S1.01	15 Summer	1	+0%	1/15 Summer			
S1.002	S1.02	15 Summer	1	+0%	1/15 Summer			
S2.000	S2.00	15 Summer	1	+0%	1/15 Summer	100/15 Summer		
S1.003	S1.03	15 Winter	1	+0%	1/15 Summer			
S1.004	S1.04	360 Winter	1	+0%	1/15 Summer			
S3.000	S3.00	15 Summer	1	+0%				
S1.005	S1.05	15 Summer	1	+0%				
S1.006	S1.06	15 Summer	1	+0%				
S1.007	S1.07	15 Summer	1	+0%				
S4.000	S4.00	15 Summer	1	+0%				
S4.001	S4.01	15 Summer	1	+0%				
S4.002	S4.02	15 Summer	1	+0%	100/15 Summer			
S4.003	S4.03	15 Summer	1	+0%	100/15 Summer			
S4.004	S4.04	15 Summer	1	+0%	100/15 Summer			
S4.005	S4.05	15 Summer	1	+0%	100/15 Summer			
S5.000	SMUGA	120 Summer	1	+0%				
S5.001	S18	120 Summer	1	+0%	2/60 Summer			
S6.000	S3G Pitch	360 Summer	1	+0%				

©1982-2020 Innovyze

Renaissance Assoc.		Page 9						
Carvers Warehouse 77 Dale Street Manchester M1 2HG								
Date 08/09/2023 11:33 File 230901 model.MDX								
Designed by HenryWilkinson Checked by								
Innovyze		Network 2020.1.3						
1 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm								
PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S1.000	S1.00	73.551	0.191	0.000	0.79	13	57.3	SURCHARGED
S1.001	S1.01	73.544	0.393	0.000	0.82	23	57.5	SURCHARGED
S1.002	S1.02	73.539	1.104	0.000	0.63	36	44.3	SURCHARGED
S2.000	S2.00	73.531	0.866	0.000	0.14		15.8	SURCHARGED
S1.003	S1.03	73.531	1.226	0.000	0.23		26.3	SURCHARGED
S1.004	S1.04	73.691	1.471	0.000	0.07		8.7	SURCHARGED
S3.000	S3.00	72.475	-0.125	0.000	0.07		3.1	OK
S1.005	S1.05	71.800	-0.245	0.000	0.08		11.6	OK
S1.006	S1.06	71.395	-0.250	0.000	0.06		21.6	OK
S1.007	S1.07	69.627	-0.218	0.000	0.17		21.6	OK
S4.000	S4.00	73.143	-0.192	0.000	0.05		2.4	OK
S4.001	S4.01	72.889	-0.177	0.000	0.10		4.6	OK
S4.002	S4.02	72.663	-0.259	0.000	0.04		4.6	OK
S4.003	S4.03	72.279	-0.257	0.000	0.05		4.6	OK
S4.004	S4.04	72.209	-0.193	0.000	0.27		28.2	OK
S4.005	S4.05	71.724	-0.156	0.000	0.20		28.3	OK
S5.000	SMUGA	70.022	-0.183	0.000	0.08	17	9.1	FLOOD RISK
S5.001	S18	69.529	-0.025	0.000	0.17		8.9	OK
S6.000	S3G Pitch	70.236	-0.179	0.000	0.09	328	4.5	FLOOD RISK
PN	US/MH Name	Level Exceeded						
S1.000	S1.00							
S1.001	S1.01							
S1.002	S1.02							
S2.000	S2.00							
S1.003	S1.03							
S1.004	S1.04							
S3.000	S3.00							
S1.005	S1.05							
S1.006	S1.06							
S1.007	S1.07							
S4.000	S4.00							
S4.001	S4.01							
S4.002	S4.02							
S4.003	S4.03							
S4.004	S4.04							
S4.005	S4.05							
S5.000	SMUGA							
S5.001	S18							
S6.000	S3G Pitch							
©1982-2020 Innovyze								

Renaissance Assoc.		Page 11
Carvers Warehouse 77 Dale Street Manchester M1 2HG		
Date 08/09/2023 11:33 File 230901 model.MDX		
Designed by HenryWilkinson Checked by		
Innovyze		Network 2020.1.3

2 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	7
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.360
Region	England and Wales	Cv (Summer)	1.000
M5-60 (mm)	18.000	Cv (Winter)	1.000

Margin for Flood Risk Warning (mm)	400.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)

Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 10080
Return Period(s) (years)	1, 2, 30, 100
Climate Change (%)	0, 0, 0, 45

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	S1.00	15 Summer	2	+0%	1/15 Summer			
S1.001	S1.01	15 Summer	2	+0%	1/15 Summer			
S1.002	S1.02	15 Summer	2	+0%	1/15 Summer			
S2.000	S2.00	15 Summer	2	+0%	1/15 Summer	100/15 Summer		
S1.003	S1.03	15 Winter	2	+0%	1/15 Summer			
S1.004	S1.04	360 Winter	2	+0%	1/15 Summer			
S3.000	S3.00	15 Summer	2	+0%				
S1.005	S1.05	15 Summer	2	+0%				
S1.006	S1.06	15 Summer	2	+0%				
S1.007	S1.07	15 Summer	2	+0%				
S4.000	S4.00	15 Summer	2	+0%				
S4.001	S4.01	15 Summer	2	+0%				
S4.002	S4.02	15 Summer	2	+0%	100/15 Summer			
S4.003	S4.03	15 Summer	2	+0%	100/15 Summer			
S4.004	S4.04	15 Summer	2	+0%	100/15 Summer			
S4.005	S4.05	15 Summer	2	+0%	100/15 Summer			
S5.000	SMUGA	60 Summer	2	+0%				
S5.001	S18	60 Summer	2	+0%	2/60 Summer			
S6.000	S3G Pitch	360 Summer	2	+0%				

©1982-2020 Innovyze

[illegible]

Renaissance Assoc.

Carvers Warehouse
77 Dale Street
Manchester M1 2HG

Date 08/09/2023 11:33
File 230901 model.MDX

Innovyze

Designed by HenryWilkinson
Checked by

Network 2020.1.3

Micro Drainage

30 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000
Hot Start (mins) 0
Hot Start Level (mm) 0
Manhole Headloss Coeff (Global) 0.500
Foul Sewage per hectare (l/s) 0.000

Additional Flow - % of Total Flow 0.000
MADD Factor * 10m³/ha Storage 2.000
Inlet Coeffiecient 0.800
Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0
Number of Online Controls 3
Number of Offline Controls 0

Number of Storage Structures 7
Number of Time/Area Diagrams 0
Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR
Region England and Wales Cv (Summer)
M5-60 (mm) 18.000 Cv (Winter)

Ratio R 0.360
1.000
1.000

Margin for Flood Risk Warning (mm) 400.0

Analysis Timestep 2.5 Second Increment (Extended)
DTS Status
DVD Status
Inertia Status

OFF
ON
ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 10080
Return Period(s) (years) 1, 2, 30, 100
Climate Change (%) 0, 0, 0, 45

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	S1.00	15 Summer	30	+0%	1/15 Summer			
S1.001	S1.01	15 Summer	30	+0%	1/15 Summer			
S1.002	S1.02	15 Summer	30	+0%	1/15 Summer			
S2.000	S2.00	15 Winter	30	+0%	1/15 Summer	100/15 Summer		
S1.003	S1.03	15 Summer	30	+0%	1/15 Summer			
S1.004	S1.04	15 Winter	30	+0%	1/15 Summer			
S3.000	S3.00	15 Summer	30	+0%				
S1.005	S1.05	15 Summer	30	+0%				
S1.006	S1.06	15 Summer	30	+0%				
S1.007	S1.07	15 Summer	30	+0%				
S4.000	S4.00	15 Summer	30	+0%				
S4.001	S4.01	15 Summer	30	+0%				
S4.002	S4.02	15 Summer	30	+0%	100/15 Summer			
S4.003	S4.03	15 Summer	30	+0%	100/15 Summer			
S4.004	S4.04	15 Summer	30	+0%	100/15 Summer			
S4.005	S4.05	15 Summer	30	+0%	100/15 Summer			
S5.000	SMUGA	30 Summer	30	+0%				
S5.001	S18	30 Summer	30	+0%	2/60 Summer			
S6.000	S3G Pitch	120 Summer	30	+0%				

©1982-2020 Innovyze

Renaissance Assoc.						Page 16			
Carvers Warehouse 77 Dale Street Manchester M1 2HG									
Date 08/09/2023 11:33 File 230901 model.MDX				Designed by HenryWilkinson Checked by					
Innovyze				Network 2020.1.3					
30 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm									
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	
S6.001	S23	360 Summer	30	+0%	30/60 Summer				
S5.002	S25	30 Summer	30	+0%					
S1.008	S1.08	30 Summer	30	+0%	100/15 Summer				
S7.000	S2G Pitch	360 Summer	30	+0%					
S1.009	S1.09	30 Summer	30	+0%	100/15 Summer				
S1.010	S1.10	60 Summer	30	+0%	100/15 Summer				
S1.011	S1.11	120 Summer	30	+0%	30/15 Summer				
S8.000	S5.00	15 Summer	30	+0%					
S8.001	S5.01	15 Summer	30	+0%	100/30 Summer				
S9.000	S28	15 Summer	30	+0%					
S1.012	S1.11	240 Winter	30	+0%	1/15 Summer				
PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S6.001	S23	70.265	0.129	0.000	0.11			11.2	SURCHARGED
S5.002	S25	69.646	-0.128	0.000	0.68			59.9	OK
S1.008	S1.08	69.274	-0.176	0.000	0.59			164.0	OK
S7.000	S2G Pitch	69.507	-0.188	0.000	0.06		216	8.9	FLOOD RISK*
S1.009	S1.09	68.509	-0.193	0.000	0.64			168.6	OK
S1.010	S1.10	68.476	-0.053	0.000	0.34			116.7	OK
S1.011	S1.11	68.377	0.103	0.000	0.12			61.6	SURCHARGED
S8.000	S5.00	69.122	-0.153	0.000	0.22			10.4	OK
S8.001	S5.01	68.927	-0.144	0.000	0.28			36.9	OK
S9.000	S28	69.275	-0.125	0.000	0.07			4.5	OK
S1.012	S1.11	67.970	0.321	0.000	0.13			59.6	SURCHARGED
PN	US/MH Name	Level Exceeded							
S6.001	S23								
S5.002	S25								
S1.008	S1.08								
S7.000	S2G Pitch								
S1.009	S1.09								
S1.010	S1.10								
S1.011	S1.11								
S8.000	S5.00								
S8.001	S5.01								
S9.000	S28								
S1.012	S1.11								
©1982-2020 Innovyze									

Renaissance Assoc.

Carvers Warehouse
77 Dale Street
Manchester M1 2HG

Date 08/09/2023 11:33
File 230901 model.MDX

Designed by HenryWilkinson
Checked by

Innovyze

Page 17



Network 2020.1.3

100 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Hot Start (mins) 0

Hot Start Level (mm) 0

Manhole Headloss Coeff (Global) 0.500

Foul Sewage per hectare (l/s) 0.000

Additional Flow - % of Total Flow 0.000

MADD Factor * 10m³/ha Storage 2.000

Inlet Coeffiecient 0.800

Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0

Number of Online Controls 3

Number of Offline Controls 0

Number of Storage Structures 7

Number of Time/Area Diagrams 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR

Region England and Wales Cv (Summer) 1.000

M5-60 (mm) 18.000 Cv (Winter) 1.000

Ratio R 0.360

Margin for Flood Risk Warning (mm) 400.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS Status OFF

DVD Status ON

Inertia Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 10080

Return Period(s) (years) 1, 2, 30, 100

Climate Change (%) 0, 0, 0, 45

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	S1.00	15 Winter	100	+45%	1/15 Summer			
S1.001	S1.01	15 Summer	100	+45%	1/15 Summer			
S1.002	S1.02	15 Winter	100	+45%	1/15 Summer			
S2.000	S2.00	15 Summer	100	+45%	1/15 Summer	100/15 Summer		
S1.003	S1.03	15 Summer	100	+45%	1/15 Summer			
S1.004	S1.04	240 Winter	100	+45%	1/15 Summer			
S3.000	S3.00	15 Summer	100	+45%				
S1.005	S1.05	15 Summer	100	+45%				
S1.006	S1.06	15 Summer	100	+45%				
S1.007	S1.07	15 Summer	100	+45%				
S4.000	S4.00	15 Summer	100	+45%				
S4.001	S4.01	15 Summer	100	+45%				
S4.002	S4.02	15 Summer	100	+45%	100/15 Summer			
S4.003	S4.03	15 Summer	100	+45%	100/15 Summer			
S4.004	S4.04	15 Summer	100	+45%	100/15 Summer			
S4.005	S4.05	15 Summer	100	+45%	100/15 Summer			
S5.000	SMUGA	15 Summer	100	+45%				
S5.001	S18	15 Summer	100	+45%	2/60 Summer			
S6.000	S3G Pitch	30 Summer	100	+45%				

©1982-2020 Innovyze

